

Swamini Enterprises

GST-27CRVPP5856R1Z9

Contact	Alpesh 9579558088	email ID	swaminientp0909@gmail.com
Quote No	24/025	Date	13-Sep-24
Customer Info	Joshh Powai		

Decsription

Sr No	ITEMS	qty	Unit	Unit price	Amount
1	Providing and applying Royal Paint on wall & Ceiling of approved make & shade filling the dents with approved Acrylic putty gypsum / or approved crack filler, binder, cleaning and making the surface dust free, preparing surfaces, applying a coat of sealer or primer as per the manufacturers specifications, applying two under coats and one finished coat of paint to achieve the required finish including scrapping the existing paint, scaffolding, cleaning etc. complete as per detail drawing, as specified and as directed	6776	Sqft	45	304920
2	carefully Removing of existing wall pepar	2800	Sqft	12	33600
3	Providing and applying Dump prof Paint on wall of approved make & shade filling the dents with approved Acrylic putty gypsum / or approved crack filler, binder, cleaning and making the surface dust free, preparing surfaces, applying a coat of sealer or primer as per the manufacturers specifications, applying two under coats and one finished coat of paint to achieve the required finish including scrapping the existing paint, scaffolding, cleaning etc. complete as per detail drawing, as specified and as directed by Engineer-in-charge	2200	Sqft	40	88000

4	Providing and fixing in position dado tile of approved make & shade on any surface as per details in drawing and Over 12 mm thk bed of cement mortar 1:3 (cement : fine sand) with thick grey cement slurry, with hairline . The job including cutting of tiles & making smooth edges wherever required . The work shall also include cost of materials, wastages, labour, all lead and lift at all levels, loading and unloading, transportation, curing etc. and all other incidental charges etc. Complete as specified in the drawing & to the satisfaction of the Site Engineer. Ceramic wall tile (Printed) With customize line work	150	Sqft	320	48000
5	Tiles hairline joints using Epoxy Joint	150	Sqft	40	6000
Terms and conditions		Subtotal			480520
Work can start only afer receiving PO		Tax 18%			86493.6
		Total			567013.6