

COPPER CHIMNEY: BANDRA WEST

QUOTE FOR COLUMNS REBARRING & MS WORK (ISMB)

S.NO	DESCRIPTION	UNIT	NOS	LENGTH	WIDTH	HEIGHT	TOTAL QTY	RATE	AMOUNT
1	RE-BARING ON COLUMNS OF SIZE 450X600X3000	NOS	9	0.45	0.6	3	9	45000	4,05,000.00
	Providing and doing rebarring on existing columns by <b>Column Jacketing method</b> including rebarring with chemical fasteners and then doing concrete and necessary shutterings including all the required tools, equipments etc all complete.								
2	Providing & installation of ISMB of size 200mm X 100mm x 3000mm	KG	20	10			200		
						ISMB TOTAL QTY IN RFT	200		
	Considered MS RATE including Rust free Zinc primer and paint	KG				Weight 7.378kg/Rft	1475.6	200	2,95,120.00
3	P/doing Anti rust treatment on Kitchen area MS ceiling. Including scrubbing the Rust and then doing anti rust zinc primer followed by rust free coats of paint as approved	SFT					1850	40	74,000.00
4	Providing & doing membrane waterproofing on terrace area on slab & wall followed by protection plaster as required.	SFT					3500	130	4,55,000.00
							<b>TOTAL</b>		<b>12,29,120.00</b>
							GST		2,21,241.60
							<b>Total With GST</b>		<b>14,50,361.60</b>

