



Electech Enterprises

ELECTRICAL CONTRACTOR & ENGINEERS

Date 01-07-2024

QUOTATION FOR IRISH HOUSE HYDERABAD

SR.NO	PARTICULARS	QUANTITY	UNIT	RATE	AMOUNT
1	Supply & Installation of SMDB	1	Nos	3,85,000	3,85,000
	Incomer:- 250A TP MCCB Thermal Magnetic Based-1 NOS+ELR Trip				
	Outgoing:-				
	20/25A SP MCB-6 Nos				
	63/125A TP MCCB-2 Nos				
	20/32A FP RCBO 30MA-12 Nos				
	Dol Starter - 4 Nos				
	200A FP Contactor				
	Emergency Push Button				
	Multifunction meter				
	CBCT with ELR				
	Voltmeter				
	Ammeter				
	Voltage selector switch				
2	Supply & Laying of Cat-6 Wire for data in 25mm Gi Conduit	350	Mtrs	350	1,22,500
3	Supply & Laying of 4+1 cable in 25mm Gi Conduit for CCTV	380	Mtrs	365	1,38,700
4	Supply & Installation of 300 x 50 Gi Cable tray	20	Mtrs	1,300	26,000
5	Supply & Installation of Single Data outlet	10	Nos	450	4,500
6	Supply & Installation of Dual Data outlet	10	Nos	650	6,500
	TOTAL AMOUNT				6,83,200
	ADD:- GST @ 18%				1,22,976
	TOTAL AMOUNT				8,06,176

Amount in words:- Eight Lakhs Six Thousand One Hundred and Seventy Six Only