



## Sri Aruna Interior Decorations

All kinds of Interior, Demolition and Tank Cleaning Works. Also, Scrap items Takers  
#58, 3rd Cross, Saibabanagar, Srirampuram, Bangalore - 560021

Mr. A. Sathya

+91 8880777145 / 9980407145  
sathya7145@gmail.com

### QUOTATION

To,  
Travel Food Services Pvt Ltd  
Site: Airport BLR BD ( Domestic)  
Subject: Signage work

Date: 02nd Dec 2024  
Quotation No.: SAI - 70/24-25  
P.O No.:  
P.O Date:

Client GSTIN:

Contact Person:

MR.Double  
prakasam

S.NO.	PARTICULARS	SPECIFICATION	Sizes	UOM	QTY	RATE	AMOUNT
1	Inside Outlet Wall 01	LG/3M cut vinyl sticker to be pasted on backwall 5132 mm (W) x 1154 mm (H)		SFT	104	240	24960
2	Left Side wall of FDU	LG/3M cut vinyl sticker to be pasted on backwall 1224 mm (W) x 2320 mm (H)		SFT	41	240	9840
3	Inside Outlet Wall 02	LG/3M cut vinyl sticker to be pasted on backwall 1942 mm (W) x 2269 mm (H)		SFT	42	240	10080
4	Inside Outlet Wall Posters Left Side	Light brown wooden frame poster 950 mm (W) x 1535 mm (H)		Nos	3	10500	31500
5	Inside Outlet Wall Posters Right Side	Light brown wooden frame poster 950 mm (W) x 1535 mm (H)		Nos	2	10500	21000
6	Wooden flooring removal	Exisitng wooden floring removal as to be done till as per the Counter Partion edges starts and if any damages as happened and same as to be fixed		SFT	150	150	22500
7	FDU Counter Modification	Wooden counter extension with 100mm thickness Korean top finishing as per provided and approved Layout with proper finishing		Ls	1	185000	185000
8	POS Counter Extension	Wooden counter extension Korean top finishing with below counter setup for wooden racks with partition and doors, and providing till box counter as per provided and approved Layout with proper finishing		Ls	1	220000	220000
9	Tiles Work	2'*2' tiles Fixing need to be lay after removal of Wooden Flooring		Ls	1	30000	30000
10	Coffee Machine Shifting	Need to shift the Coffee machine at POS counter same below that water inlet and drain outlet supply as to be provided from the exisitng plumbing line spec		Ls	1	140000	140000
11		Coffee Machine 3 phase electrical need to provide till LT panel (32A 4 pole MCB with Industrial Plug top set)		Ls	1	20000	20000
12		Tiles Removing and fixing work for laying new RO water line and Drain line		Ls	1	25000	25000
13	Entrace SS Floor beeding	Need to Lay the SS floor beeding as per exisitng spec		RFT	35	450	15750

Total In Numbers: ₹ 8,91,643.40

Total In Words:

<b>Taxable Amount</b>	₹ 7,55,630.00
<b>CGST @ 9%</b>	₹ 68,006.70
<b>SGST @ 9%</b>	₹ 68,006.70
<b>IGST @ 18%</b>	
<b>Round Off</b>	
<b>TOTAL</b>	₹ 8,91,643.40

#### Other Payment Terms and Conditions

- 100% Advance payment on order
- Work Order should be release before starting work
- Net 30, which means payment is due 30 days from the invoice date
- After receiving advance payment it can take 2-3 days to start work

Company's GSTIN: 29BFBPA0210H1Z9

Company's Bank Details:

Sri Aruna Interior Decorations  
Bank: ICICI Bank  
A/c No. 007805500596  
IFSC: ICIC0000078  
Branch: Malleshwaram, Bangalore

For Sri Aruna Interior Decorations

*Sathya*  
Authorized Signatory