

Shah Enterprises

SL NO	PO NO	DESCRIPTION OF WORK	UNIT	QTY	RATE	AMOUNT
1	Semolina/PO/24-25/000896	P F of MS Framework with 50mm x 50mm x 16 gauge MS tube framing out of vertical members at 600mm c c with horizontal members at 600 mm c c, the framework b or w main MS members by welding to fix cement board on it. Area: Kitchen Back Wall Partition	Sqm	6.2	3577	22177.4
3	Semolina/PO/24-25/000848	Providing and laying in position cement concrete of specified grade excluding the cost of centring & shuttering all work upto 60 mm from existing lvl. 1:4:8 (1 cement: 4 coarse sand: 8 graded stone aggregate 40mm nominal size) Area: FOH	Sqm	9.56	1161	11099.16
TOTAL						33,277