

SAI SHRUSHTI INTERIOR

Room No 254 Ambegoan chal No 02 Gholai Nagar Kalwa) Thane Mob : 9768141314 / 9892841890 / 8286255093 E mail : saishrushtiinteriors@gmail.com

Quotation

TO,
Josh Pawai
Powai mumbai

Date : 13-09-2024
QTY NO -19

Sr. No	Particulars	Qty	unit	Rate	Amount
1	Providing and applying Royal Paint on wall & Ceiling of approved make & shade filling the dents with approved Acrylic putty gypsum / or approved crack filler, binder, cleaning and making the surface dust free, preparing surfaces, applying a coat of sealer or primer as per the manufacturers specifications, applying two under coats and one finished coat of paint to achieve the required finish including scrapping the existing paint, scaffolding, cleaning etc. complete as per detail drawing, as specified and as directed	6776	SQFT	35	237160.00
2	carefully Removing of existing wall pepar	2800	SQFT	8	22400.00
3	Providing and applying Dump prof Paint on wall of approved make & shade filling the dents with approved Acrylic putty gypsum / or approved crack filler, binder, cleaning and making the surface dust free, preparing surfaces, applying a coat of sealer or primer as per the manufacturers specifications, applying two under coats and one finished coat of paint to achieve the required finish including scrapping the existing paint, scaffolding, cleaning etc. complete as per detail drawing, as specified and as directed by Engineer-in-charge.	2200	SQFT	25	55000.00
4	Providing and fixing in position dado tile of approved make & shade on any surface as per details in drawing and Over 12 mm thk bed of cement mortar 1:3 (cement : fine sand) with thick grey cement slurry, with hairline . The job including cutting of tiles & making smooth edges wherever required . The work shall also include cost of materials, wastages, labour, all lead and lift at all levels, loading and unloading, transportation, curing etc. and all other incidental charges etc. Complete as specified in the drawing & to the satisfaction of the Site Engineer. Ceramic wall tile (Printed) With customize line work	150	sqft	260	39000.00
5	Tiles hairline joints using Epoxy Joint	150	sqft	30	4500.00
					358060.00

GST NO: 27AOWPP5957MIZO

NOTE This Quantity is Approximately
All Tax Extra
Any Extra work charge will be Extra

For SAI SHRUSHTI INTERIOR

ANAND