

**COMPANY NAME: TRAVEL FOOD SERVICES PVT. LTD.**  
**TENDER DOCUMENT FOR UNA BIKANERVALA KITCHEN'S**  
**EQUIPMENT**

**1. GENERAL TERMS AND CONDITIONS**

**2. GENERAL METAL SPECIFICATIONS**

**3. INDIVIDUAL EQUIPMENT SPECIFICATIONS**

**4. BOQ OF KITCHEN EQUIPMENT**

**5. KITCHEN LAYOUT**

## **GENERAL TERMS AND CONDITIONS**

### **Prices:**

- Quoted prices shall be in Indian Rupees.
- Prices quoted should be basic ex-factory prices.
- All other additional Extras to be mentioned separately.

### **Delivery:**

- Tenderer shall clearly indicate the production time required for the said volume of the order in terms of weeks from the date or receipt of order.
- Delivery of material induces responsibility of off-loading the goods and shifting the goods at the location of installation.

### **Site Study / Measurement:**

It will be responsibility of the Tenderer to take site visit for its study and detail measurement before starting the manufacturing of the equipment and co-ordinate with the consultant for smooth progress of the work. Fitting of equipment in to given locations will be total responsibilities of the manufacturer which must be noted. Oversized and / or undersized equipment due to site conditions will be rejected and appropriate size of product shall be fabricated by the supplier at his cost.

### **Samples of fittings:**

To be used like Handles; locks; faucet hinges etc. Shall be sent for an approval of the consultant prior to use.

### **Approval of Shop Floor Drawings:**

All the Individual Drawings should be sent to consultant for his approval. All the Drawings wherever changes are indicated by the consultant shall be rectified and sent back to the consultant for his approval.

### **Midway Inspection:**

Though it is not insisted, it will be in the interest of the supplier to organize midway inspection by consultant to avoid changes on completed products. Expenditure for this Inspection shall be to Supplier's Account.

### **Final Inspection:**

On completion of the final products supplier shall organize for Factory Inspection of all the products prior to dispatch. Expenditure for this Inspection shall be to Supplier's Account.

**Commissioning:**

Supplier shall organize for complete manpower for Commissioning and expenditure for lodging boarding shall be to Supplier's Account.

**Penalty Clause:**

Delivery period being essence 2% of the order value shall be charged for every day's delay as penalty and shall be adjusted in the final Bill.

**Deviation to Specifications:**

Any deviation to the specifications given in tender document must be clearly listed out point wise on separate sheet, in following format.

ITEM'S NUMBER AND NAME	TENDER SPECIFICATION	OFFERED SPECIFICATIONS

**Payments Terms:**

- 25% Advance against Bank Guarantee.
- 50% Against Delivery of complete order at site.
- 20% Against Commissioning.
- 05% After 6 months of working.

**Spare Parts:**

Supplier should provide recommended list of spare for 1st year with quantity and shall quote for it separately.

**AMC Contract:**

Tenderer shall send along with this offer a separate offer for comprehensive AMC contract of products supplied for three years on completion of the guarantee period.

**Client :**

Reserves the rights of accepting the tender in part or rejecting it fully without giving any reasons.

## **GENERAL METAL SPECIFICATIONS FOR KITCHEN EQUIPMENT**

### **TOPS:**

Made of 16 swg. 304 Quality 18/8 Grade Stainless Steel duly 120 Grit matt polished with all resulting edges rounded with no bur or other excess material left. Top will be turned down 50mm and 12mm underneath in channel shape on all exposed sides, in case of sunk in tops wherever mentioned the sides shall be raised by 20mm on all exposed sides, where tables are placed against walls, they will be turned up at back approximately 100/150mm splash back returned 25mm at 45° to wall with all exposed ends closed, argon arc welded and smooth polish.

### **UNDERSIDES:**

Undersides of all Stainless Steel Tops for Table Counters, Sinks, Dish and Pot Tables will be mounted on 30mm x 30 mm x 5mm Stainless Steel Angle frame work with cross supports at maximum of 750mm span, duly secured by welding. The underside will be suitably sound deadened by treating with a coat of aluminum carboxide rubberized paint, finished with silver paint.

### **UNDERSHELVES:**

Under shelves wherever called for will be constructed of 18 swg 304 Quality Stainless Steel Sheet uniformly matt polished with 120 Grit and reinforced with 30mm x 30mm x 3mm Stainless Steel angle frame. All shelves will be turned down 38mm and 12mm underneath on all sides with resulting corners cutout to fit contour of leg. Shelves for Hot case will be perforated.

### **FRAMEWORK:**

Units with side panels shall have framework of **30mm x 30mm x 3mm Stainless Steel Angles** maximum distance will be 750mm.

### **LEGS/UPRIGHTS:**

All Legs/Uprights will be constructed of 38mm Ø 16 swg Stainless Steel 304 B salem quality tubes spaced not more than 1800mm on center. All Legs will be fitted with Ferro nylon adjustable to approximately 30mm Height. Units more than 1800 mm in length will have 3 pairs of Uprights.

### **CROSS BRACINGS:**

Front to back forming a 'H' frame wherever required will be constructed of 25mm Ø mm 16 swg Stainless Steel 304 tubes. All Cross Bracings will run horizontal and level between all legs approximately 150mm above floor level. All joints will be completely welded around entire perimeter forming a complete seal, with all welds ground and polished to match adjacent work.

### **SINKS:**

All Sinks will be constructed of 16 swg 304 quality Stainless Steel with radius corners, argon arc welded, smooth ground and uniformly finished, duly fitted with 38 mm Ø BSP drain coupling and 1½" BSP Ball Valve, and /OR faucet as mentioned in Individual Input listing.

### **STAINLESS STEEL STORAGE RACK:**

Shelves will be made of 18 swg 304 Stainless Steel Sheeting. The Rack will have number of shelves as specified in the description and reinforced with 25mm x 100mm x 25mm inverted 16 Swg Stainless Steel channel. Uprights of 38mm Ø x 16 swg Stainless Steel pipes fitted with nylon bullet feet.

### **BAIN MARIEWATER CHAMBER AND GN PANS.:**

Made from 18 swg Stainless Steel 304, radius corner construction argon arc welded fitted with 25 mm Ø BSP lever operated drain valve for easy drain out and provided with cavity to house water immersion heater for efficient heating & duly insulated suitably. The unit will have a water sensor. The G/N pan used will be Imported and each with flat lid. (if possible to have cut for ladle)

### **INTERIOR OF HOT CABINET/PLATEWARMER:**

All vertical interior panels of Hot Cabinet's and Plate Warmers will be constructed of 20 swg 304 Quality, 18/8 Grade Stainless Steel double beeded panels duly insulated with 1" thick glass wool insulation with thermostatic control from 0-110° C. Thermostat is of EGO make (Germany) miniature circuit breaker is to be used for protection. The control panel is die pressed and to be flush with the front. The heating elements at the bottom shall be covered with full size stainless steel perforated panel.

### **SLIDING DOORS:**

Wherever provided to Ambient Cabinets as Non - Insulated the same will be constructed of 18 swg Stainless Steel 304, beeded panels and Insulated doors will be constructed of 20 swg Stainless Steel 304, beeded sandwiched panels duly mounted on top hung easy rolling nylon rollers and Stainless Steel guiding rails below.

### **BLINDER /ENCLOSURES:**

Made of 20 swg Stainless Steel Sheeting uniformly polished and duly beeded from all sides.

### **OVERHEAD SHELVES:**

Wherever provided will be made of 18 swg Stainless Steel 304 double beeded on all sides duly reinforced and fixed on 25mm x 25 mm 16 swg Stainless Steel pipes at the height specified and reinforced with 20mm x 60mm x 20mm 16 swg Stainless Steel channels.

### **WALL SHELVES:**

Made of 18 swg Stainless Steel Sheet 304 with 25mm and 12mm double beeding all 3 sides and double beeded downwards at front duly secured with 16 swg Stainless Steel wall brackets. The brackets are fixed by anchor fasteners on wall.

### **WALL STORAGE CABINET:**

Provided with of 18 swg Stainless Steel 304, Hinged Doors wherever mentioned not exceeding 400mm length. Doors shall be provided with pad lock facility. The construction shall be reinforced beeded panels and shall be fixable with anchor fasteners on wall.

### **FRONT/CONTROL PANEL:**

All equipment will have the front panel made of 18 swg Stainless Steel 304, duly beeded and die pressed 20 swg Stainless Steel recessed control panel for safety operation, wherever provided.

### **SS POT RACK:**

Sides and Uprights of 38 mm Ø Stainless Steel 304 pipes while Shelves made of 25 mm Ø Stainless Steel 304, pipes fitted at 100 mm C to C distance.

### **ELECTRICALS:**

All electrically operated equipment will be thermostatically controlled with indicating bulbs duly fitted with best quality Brand Heaters or equivalent and heat resistant fiber coated copper wire. Miniature circuit breaker is used for protection of the equipment heaters. Electrical Hot Plates are manually controlled without thermostat.

### **GAS EQUIPMENT:**

All gas equipment will be duly connected with best quality copper pig tails, needle valves and burners will be off heavy duty industrial type and to be operated at 0.3 kg /cm<sup>2</sup> (4.5 PSIG) gas pressure. The main line will be of 25 mm Ø BSP 'C' Class ERW M/ S Pipe and pressure tested. All gas equipment's will have pilot.

### **INSULATION:**

All equipment will be suitably insulated with 25mm thick high quality mineral glass wool/asbestos/cerwool. Oven, bulk cookers will be insulated with 65mm thick glass wool.

### **ARGON WELDING:**

Argon welding should be used for fabrication of equipment. The welded joints are smooth polished.

### **GRANITE TOPS:**

Wherever called for will be of 20mm thick Black/White marble duly placed on neoprene rubber strips and framed with 16 swg Stainless Steel all sides to prevent slipping.

### **FREEZING EQUIPMENT**










All frameworks will be Stainless Steel angle duly covered with 20 swg Stainless Steel Salem quality. Inner 22 swg 304 quality with PUF insulation fitted with Kirloskar hermetically sealed compressor.

### **FITTING**

All nuts, bolts, screws to be of SS 304.

### **DETAILS OF ELECTRICAL, GAS & PLUMBING INPUTS TO BE USED**

1	Water Immersion Heaters	:	Escort / Spot – Heat / Vileco (Girish Electricals)
2	Stainless Steel Tubing Oil Immersion Heater (Liftable)	:	S.V. Enterprise / Spot – Heat / Vileco (Girish Electricals)
3	Air Heater Encoly Tubing	:	S.V. Enterprise / Spot – Heat / Vileco (Girish Electricals)
4	Thermostat	:	EGO Make / Zumo
5	Rotary Switch	:	Thakur / Trinity Electricals / Kay Bee
6	Neon Indicating Lamps	:	S.V. Enterprise
7	Burners	:	Standard Make / United Make
8	Castors	:	Rexello Castors / Bombay Star
9	Compressors	:	Kirloskar Copeland / Shriram
10	Faucet	:	Jaquar / Cieko / ARK
11	Motor	:	Crompton / Siemens / New India / Hindustan / Kirloskar

FABRICATED DETAILS SHEET	
WORK TOP DETAILS	
PLAIN TOP	PLAIN TOP WITH SPLASH DETAILS
 <p>35mm x 35mm x 3mm SS Angle Frame.</p>	 <p>35mm x 35mm x 3mm SS Angle Frame.</p>
SUNK IN TOP	SUNK IN TOP WITH SPLASH DETAILS
 <p>35mm x 35mm x 5mm SS Angle Frame.</p>	 <p>35mm x 35mm x 5mm SS Angle Frame.</p>
SPLASH DETAILS	UNDERSHELVES FIXING DETAILS
	<p>38mmØ x 16 swg SS pipe / legs with adjustable nylon bullet feet.</p>   <p>30mm x 30mm x 3mm SS Angle Frame.</p>
RACK SHELVES FIXING DETAILS	
<p>38mmØ x 16 swg SS pipe / legs with adjustable nylon bullet feet.</p> 	 <p>12mm x 25mm x 100mm x 25mm x 12mm Hat type SS stiffener at bottom</p>




**PRODUCT : TABLE TOP REFRIGERATOR WITH BAIN MARIE.  
TABLE TOP REFRIGERATOR.  
REFRIGERATOR PICK UP COUNTER.**

Note:- Please do not provide Build in Lock.  
Provision for External Locking to be provided.




Locking Facility


**FOOD WARMER:-**



18 swg SS 304 grade R.R. with 750 watt. Air heater with toggle switch on both sides.



Door Design (Insulated)




Flushed Door as detailed

Top:-	304 Grade, 18 swg Stainless Steel.
Refrigerated Pan:-	Double walled 20 swg Stainless Steel Coiled Pan.
Containers:-	Gastronom size as referred in Individual drawings.
Over Head Shelves:-	304 Grade, 18 swg Stainless Steel, double beaded on all sides duly reinforced and fixed on 25mm Ø, 16 swg Stainless Steel tubular pipes.
Food warmers:-	-
Outer/Inner Body:-	20/22 swg Stainless Steel.
Temp. Indicator:-	Special non- clogging electronic indicator with built in power supply with ON/OFF switch on the front panel of the compressor.
Temp. :-	4° to 8° Celsius.
Doors :-	304 Grade, 22 swg Stainless Steel, spring loaded, self closing door with magnetic gasket.
Insulation :-	PUF Insulation.
Refrigerant :-	R 134 A.
Refrigeration System :-	Hermetically sealed Kitoskar Copeland compressor with AUE fan motor.

Plain Top shall be Forced Draft Cooling Unit,  
Unit with Refrigerated bain Marie shall have Static Cooling.

Pan resting :-	Made of 10mm x 15mm x 10mm, 18 swg Stainless Steel channel pairs with 15mm top edge cut to rest the pan before sliding. 6 pairs behind each door fitted equidistant on Stainless Steel channel for proper air circulation.
Base Frame:-	32mm x 32mm SS square pipes or 30mm x 30mm x 3mm SS Angle Frame (304 swg)
SS Rack:-	3 Nos. Stainless Steel racks of Stainless Steel rods provided in each compartment. sides and 2 cross supports of 6mm, while shelf of 4mm Stainless Steel rods.
Legs / Castors:-	150mm Ø Heavy Duty Rubberised Castors with Locking arrangement.



BIKANERVALA  
KITCHEN@UNA



# TRAVEL FOOD SERVICES

STATUS OF RELEASE:					
<input checked="" type="checkbox"/>	FOR APPROVAL	<input type="checkbox"/>	FOR TENDER		
<input type="checkbox"/>	FOR DISCUSSION	<input type="checkbox"/>	FOR CONSTRUCTION		
REV.	DATE	PREP BY	CHK BY	APPVD BY	REMARK

STAMP:	
PROJECT NAME:	#GRUB HUB@UNA
CLIENT NAME:	
ARCHITECT:	TFS

DRAWING TITLE:				
BIKANERVALA & GIANI'S @ UNA KITCHEN LAYOUT				
DRAWING NO:				
NORTH	DRAWING NO	Rev.		
SCALE	DATE	PREP	CHKD	APPVD
	15-12-2023	NIROJ SHRIWAL	MANISH	RITUPARN SHARMA

#GRUB HUB@UNA

S. No.	Equipment	Dimensions	Qty	Category	Wattage(KW)	Elec. Point Ht.	Water supply Height	Drain	Gas & GLDS Point	Exhaust	BRAND	REMARKS	Category
BIKANERVALA													
BK-01	DOSA BAIN MARIE (600WX700DX850H)	(600WX700DX850H)	1	Fabrication					GAS 250MM	YES			
BK-02	SINGLE BURNER RANGE (700WX700DX850H)	(700WX700DX850H)	1	Fabrication					GAS 250MM	YES			
BK-03	HANDWASH SINK (400Wx450Dx850H+200HIGH)	(400Wx450Dx850H+200HIGH)	1	Fabrication			450MM/FFL	YES					
BK-04	SOUP TUREEN (CASSELIN)	AS/SELECTION	1	Boughtout	0.5	1050MM/FFL					CASSELIN		
BK-06	SS WORK TABLE (1200Wx700Dx850H)	(1200Wx700Dx850H)	1	Fabrication									
BK-07	SS WORK TABLE (450Wx600Dx850H)	(450Wx600Dx850H)	2	Fabrication									
BK-08	POT WASH RACK WITH 5 PERFORATED SHELVES (900Wx450Dx1800H)	(900Wx450Dx1800H)	1	Fabrication									
BK-09	MS POWDER COATED RACK WITH 8 SHELVES (915Wx450Dx1950H)	(915Wx450Dx1950H)	12	Boughtout									
1	DRAIN THROUGH GRATING (300x300)	(300x300)	6	OGT									
2	STRIP CURTAIN (1050WX2100H)	(1050WX2100H)	1	Boughtout		2300MM/FFL							
3	AIR CURTAIN (MITZVAH) (1050WX300D)	(1050WX300D)	1	Boughtout	0.5	2300MM/FFL							


NOTE:

1. All the dimension needs to be physically measured at site by the vendor before commencing the production..
2. G/N Pan Requirement will be shared by concerned brand.



EQUIPMENT NO: BK-02  
 EQUIPMENT NAME: Single Burner Range  
 SIZE-: 700WX700DX850HT.  
 QTY-: 01  
 BRAND: AS/SS  
 MANUFACTURER SPEC.


NO.16SWG SS304 TOP W/FRONT TURNED DOWN 50MM & IN 12MM & BOTH SIDES TURNED DOWN 50MM RAW & REAR SIDE TO BE TURNED UP 150MM OUT 25MM & DOWN 12MM SECURED WITH SS304- 40X40X3MM THK



**PLAN**

400X400MM CAST IRON REMOVABLE GRATE (1NOS.)  
 1 NOS G TYPE BURNER W/PILOT LAMP

**ISOMETRIC VIEW**



**ELEVATION A**

**SECTION AT B-B**

BIKANERVALA

**TRAVEL FOOD SERVICES**

STATUS OF RELEASE: <input type="checkbox"/> FOR APPROVAL <input type="checkbox"/> FOR TENDER <input checked="" type="checkbox"/> FOR DISCUSSION <input type="checkbox"/> FOR CONSTRUCTION						STAMP:		DRAWING TITLE: UNA BIKANERVALA KITCHEN		
						PROJECT NAME: UNA FOOD COURT		DRAWING TITLE: BIKANERVALA EQUIPMENT DETAIL		
						CLIENT NAME:		NORTH	DRAWING NO	
						ARCHITECT: TFS		SCALE	DATE	PREP
REV.    DATE    PREP BY    CHK BY    APPVD BY    REMARK								13-12-2023	NIROJ SHRIWAL	RITUPARN SHARMA
								CHKD	APPVD	Rev.
								NIROJ SHRIWAL	RITUPARN SHARMA	

EQUIPMENT NO: BK-3  
 EQUIPMENT NAME:  
 Handwash Sink  
 + RO inlet




SIZE-: 400WX450DX850HT.

QTY-: 01  
 BRAND: AS/SS  
 MANUFACTURER SPEC.

EQUIPMENT NO: BK-04  
 EQUIPMENT NAME: Soup  
 Tureen

SIZE-: as/spec.

QTY-: 01



BIKANERVALA

**TRAVEL FOOD SERVICES**


STATUS OF RELEASE: <input type="checkbox"/> FOR APPROVAL <input type="checkbox"/> FOR TENDER <input checked="" type="checkbox"/> FOR DISCUSSION <input type="checkbox"/> FOR CONSTRUCTION						STAMP:		DRAWING TITLE: UNA BIKANERVALA KITCHEN			
PROJECT NAME: UNA FOOD COURT						CLIENT NAME:		DRAWING TITLE: BIKANERVALA EQUIPMENT DETAIL			
ARCHITECT: TFS						ARCHITECT:		NORTH	DRAWING NO		Rev.
REV.	DATE	PREP BY	CHK BY	APPVD BY	REMARK	SCALE		DATE 13-12-2023	PREP NIROJ SHRIWAL	CHKD NIROJ SHRIWAL	APPVD RITUPARN SHARMA

EQUIPMENT NO: BK-06


EQUIPMENT NAME: SS  
Work Table (with under &  
overhead shelf)

SIZE-: 1200WX700DX850HT.

QTY-: 01  
BRAND: AS/SS  
MANUFACTURER SPEC.



**PLAN**



**ELEVATION A**

BIKANERVALA

**TRAVEL FOOD SERVICES**

STATUS OF RELEASE:  
 FOR APPROVAL     FOR TENDER  
 FOR DISCUSSION     FOR CONSTRUCTION

REV.	DATE	PREP BY	CHK BY	APPVD BY	REMARK

STAMP:  
PROJECT NAME: **UNA FOOD COURT**  
CLIENT NAME:  
ARCHITECT: **TFS**

DRAWING TITLE: <b>UNA BIKANERVALA KITCHEN</b>				
DRAWING TITLE: <b>BIKANERVALA EQUIPMENT DETAIL</b>				
NORTH	DRAWING NO			Rev.
SCALE	DATE	PREP	CHKD	APPVD
	13-12-2023	NIROJ SHRIWAL	NIROJ SHRIWAL	RITUPARN SHARMA



EQUIPMENT NO: BK-07

EQUIPMENT NAME: SS WORK PLATE

SIZE-: 450WX600DX850HT.  
QTY-: 02

BRAND: AS/SS  
MANUFACTURER SPEC.

TOP MADE OF 16G SS304 SS SHEET  
SPLASH OF REAR SIDES 50MM HIGH



BIKANERVALA

**TRAVEL FOOD SERVICES**

STATUS OF RELEASE: <input type="checkbox"/> FOR APPROVAL <input type="checkbox"/> FOR TENDER <input checked="" type="checkbox"/> FOR DISCUSSION <input type="checkbox"/> FOR CONSTRUCTION						STAMP: PROJECT NAME: <b>UNA FOOD COURT</b>		DRAWING TITLE: <b>UNA BIKANERVALA KITCHEN</b>		
ARCHITECT: <b>TFS</b>						CLIENT NAME: _____		DRAWING TITLE: <b>BIKANERVALA EQUIPMENT DETAIL</b>		
REV.	DATE	PREP BY	CHK BY	APPVD BY	REMARK	NORTH _____		DRAWING NO _____		Rev. _____
						SCALE	DATE	PREP	CHKD	APPVD
							13-12-2023	NIROJ SHRIWAL	NIROJ SHRIWAL	RITUPARN SHARMA



EQUIPMENT NO: BK-08


EQUIPMENT NAME: Pot Wash Rack with 5 Perforated Shelves

SIZE-: 900WX450DX1800HT.


QTY-: 01

BRAND: AS/SS

MANUFACTURER SPEC.




PLAN



ELEVATION

SECTION

SS PERFORATED SHEET



BIKANERVALA

TRAVEL FOOD SERVICES

STATUS OF RELEASE:

- FOR APPROVAL     FOR TENDER  
 FOR DISCUSSION     FOR CONSTRUCTION

REV.	DATE	PREP BY	CHK BY	APPVD BY	REMARK

STAMP:

PROJECT NAME:

UNA FOOD COURT

CLIENT NAME:

ARCHITECT:

TFS

DRAWING TITLE:


UNA BIKANERVALA KITCHEN

DRAWING TITLE:


BIKANERVALA EQUIPMENT DETAIL

NORTH	DRAWING NO			Rev.
SCALE	DATE	PREP	CHKD	APPVD
	13-12-2023	NIROJ SHRIWAL	NIROJ SHRIWAL	RITUPARN SHARMA


EQUIPMENT NO: BK-09  
 EQUIPMENT NAME: MS Powder coated Rack with 8 shelves  
 SIZE-: 915WX450DX1950HT.  
 QTY-: 12  
 BRAND: AS/SS  
 MANUFACTURER SPEC.?




PLAN



ELEVATION



SECTION



BIKANERVALA

TRAVEL FOOD SERVICES

STATUS OF RELEASE:					
<input type="checkbox"/>	FOR APPROVAL	<input type="checkbox"/>	FOR TENDER		
<input checked="" type="checkbox"/>	FOR DISCUSSION	<input type="checkbox"/>	FOR CONSTRUCTION		
REV.	DATE	PREP BY	CHK BY	APPVD BY	REMARK

STAMP:	
PROJECT NAME:	UNA FOOD COURT
CLIENT NAME:	
ARCHITECT:	TFS

DRAWING TITLE: UNA BIKANERVALA KITCHEN				
DRAWING TITLE: BIKANERVALA EQUIPMENT DETAIL				
NORTH	DRAWING NO			Rev.
SCALE	DATE	PREP	CHKD	APPVD
	13-12-2023	NIROJ SHRIWAL	NIROJ SHRIWAL	RITUPARN SHARMA