

SR. NO.	DESCRIPTION	UNIT	TOTAL	RATE IN	TOTAL AMOUNT IN Rs.
1.0	FAS System				
1.1	SITC of conventional type Manual call point complete with Glass, hammer and chain etc. as required.	Nos.	1		0.00
1.2	SITC of conventional type Smoke Detector complete. as required.	Nos.	20		0.00
1.3	SITC of conventional type Heat Detector complete. as required.	Nos.	9		0.00
1.4	SITC of electronic hooters with LMT (hooters shall also be able to work as public address system sounders) housed in sheet steel / Polymer housing suitable for wall / ceiling and surface / recess mounting including making connections with wires complete in all respects and as per specifications.	Nos.	1		0.00
1.5	SITC of wall / floor type following zone (each zone accessing minimum 20 units (detectors/ devices) Conventional Type microprocessor based with LCD display main control panel fabricated from 16 SWG CRCA sheet steel sealed maintenance free (SMF) batteries of min 2 X 7AH of 12 V or as required.				
1.5.1	2 zone	Nos.	1		0.00
1.6	SITC of conventional type microprocessor based Remote Annunciator panel of following zones for wall mounting type fabricated out of 16 SWG CRCA sheet steel incorporating audio visual indication for each zone without battery bank and battery charger.	Nos.	1		0.00
1.7	Supply and drawing FRLS Fire Alarm Cable As Per IS .				
1.7.1	2 x 1.5 sq mm	Mtr	725		0.00
	TOTAL FOR MISCELLANEOUS WORKS			Rs.	0.00