

SR. NO.	DESCRIPTION	UNIT	QTY	RATE	TOTAL BOQ AMOUNT
8.0	CCTV System				
8.1	Supply Installation, testing & commissioning of Indoor type Analogue Dome Camera with 1/2" 2 Mega Pixel, integrated 4/6mm Fixed lens, Full HD high definition, Inbuilt Smart IR LED upto 10m distance, 0.02 lux color/0 lux with IR LEDs on, H.264, H.265 high profile, True Day/Night, , & 12VDC operated, ONVIF compliant, with Junction box & required accessories.	Nos.	8.00		-
8.2	Supply, installation, testing & commissioning of 16 Channel Licence Server & hardware based Digital Video Recorder (DVR) with 3 Client licence, Embedded OS & per-loaded video recording software, Minimum 256 Mbps incoming bandwidth and 256 Mbps outgoing bandwidth, 1x 1000Mbps Ports, ONVIF, H.265 high profile, 2 x HDMI & VGA output for monitor, Upto 40TB storage capacity, minimum 4 SATA Interfaces, upto 10TB capacity for each SATA, including 20TB Storage HDD (Hard Disk) @ recording resolution of 25fps @ 1080P and H.265 for 30 days, including required accessories. Vendor to submit Bandwidth & Storage calculation sheet.	Nos	1.00		-
8.3	Supply, laying, testing of RG 6 Cable for CCTV.	Mrt	450.00		-
8.4	Supply, laying, testing (for continuity) of 23 AWG Copper, Cat 6 UTP Cable, Data & Wi-Fi points including end termination, dressing, bunching of cables with identification ferruling.	Mrt	500.00		-