



Date :11-07-2024

TO

Travel Food Service,  
Chennai.

## Quotation

**Sub : T1 Departure Sangeetha drain line works.**

Dear Sir/Mam,

We are pleased to quote our prices and specification as below

Providing and fixing **Submersible Sewage Cutter Pump** 1HP with sensor (make of TEXMO ) and UPVC pipe laying from Existing shop to existing live line

- Excavation, PQC road cutting 250mm depth, granite dismantling, paver block removing.
- Backfilling excavated area, laying of concrete at PQC road, granite laying work.

S.No	Description	Rate	Amount
1	Submersible Sewage Cutter Pump 1HP with sensor	73789.00	73789.00
2	Laying UPVC pipe line ( 70 M)	83387.00	83387.00
3	Excavation, PQC road dismantling , granite dismantling, Paver block removal work ( 70 M )	55252.00	55252.00
4	Back filling, concrete filling at PQC road, Granite laying , paverblock relaying ( 70 M )	58987.60	58987.60

(A) 271415.60

Add 18% GST (B) 48854.7

Total Amount 320269.7

---

**RS.3,20,270/-**

**Amount in words :** ( Three lakhs Twenty thousand Two hundred and Seventy only )



#### **NOTES OF WORKS: TERMS AND CONDITIONS**

- If in case of any delay in work by client side of material selection, payment on time or any other quote will be revised.
- The Above Quoted rates are all inclusive Rates for Materials, Conveyance, Loading & Unloading of Materials at Site, Labour Charges and Work Supervision & Quality assurance charges. Which finally means; absolutely There is no Hidden Charges.
- 60% of amount should be paid before stating the work
- One Year Free Maintenance service
- In case any modifications are required in the given Specifications; the same Shall reflect on the Quoted Rates; as per the client's Needs & Requirements; Rates may go bit higher or lower depending on the changes.
- Water and electricity should be supplied to the contractor free of charge
- The contractor shall not be held responsible for any delay due to rain, natural calamities, and labor strike, lorry strike or for any reason, which is beyond the control of the contractor
- Anything other than mentioned in the quote will be charged extra by customer or owner of the land.
- GST will not applicable in case of cash payment

**Samundeeswari Construction**

**Y.K Paramesvar**



## SUBMERSIBLE SEWAGE PUMP WITH CUTTER

<b><u>SPECIFICATIONS</u></b>	
Brand Name	TEXMO
Cutter Blade	Stainless Steel
Impeller	High Chrome
Material	Cast Iron Pump Case
Voltage	230-380 V
Frequency	50 Hz
Phase	Single Phase
Type of Product	Sewage Water Pump
Power Rating	0.75 kW
Speed	2900RPM
Insulation Class	F Class
Rating (Kw)	0.75
Outlet Size	62mm
Power (HP)	1HP
Maximum Head	15meter
Maximum Discharge	100 to 500 LPM

### SALIENT FEATURES

- Transferring Raw Sewage from Collection Tank to Primary Settling Tank in Sewage Treatment Plants.
- Stainless Steel Shaft and Fasteners to Enhance Life.
- Chemical Resistant Coating on Impeller and Casing to Improve life and Performance.



2. Laying UPVC pipe line ( 70 M)

- we are using Ashirvad for all the pipes and fittings
- we are using UPVC 50mm dia pipes
- Pipe withstand up to 60°C without deformation
- Working Pressure 27.6 , 400 psi

3(a). Paver Removing

- Length of 23meters Paver Block Removing Work

3(b). PQC Road Dismantle

- Length of 14 meters PQC Road Cutting While Using Core Cutting upto the depth of 25mm

3(c). Granite Removing

- Length of 16 meters Granite Removing Work

3(d). Surface Excavation

- Length of 17 meters Surface Excavation work

4. Finishing

- Back filling, concrete filling at PQC road, Granite laying , paver block relaying ( 70 M )