









Sl. No.	Projects	Prifar Signs		
		Amount	GST	Total Amount
1	Shawarma, Tacos Burger, MK	350,650	63,117	413,767
	<b>TOTAL</b>	<b>350,650</b>	<b>63,117</b>	<b>413,767</b>

S.No	AREA	REFERENCE	ITEM/ DESCRIPTION	SIZE	QTY.	Rate	Amount
<b>SHAWARMA SHACK</b>							
1	Shawarma Shack Outlet Counter Signage		75 MM depth Logo shape LED cut Black Aluminium Channel box + Logo UV print on front milky white acrylic	2590 mm (W) x 300 mm (H) Size to be confirmed	1	49000	49000
2	Shawarma Shack Outlet Sign Boards		Structure details mentioned in elevation as well as in the left side column Letters will be 5mm White Acrylic	Complete Structure: 1050 mm (H) x 1230 mm (W)  Each Arrow: 150 mm (H) x 900 mm (W)	4	6500	26000
3	Shawarma Shack Outlet Left Wall Boards		Black Border Wooden Frames + Artwork will be vinyl print with 5MM Sunboard <b>Artwork will be shared later once it is finalize</b>	850 mm (H) x 600 mm (W)	2	3200	6400
4	Burger Tacos Co. Outlet Counter Signage		75 MM depth Logo shape LED cut Black Aluminium Channel box + Logo UV print on front milky white acrylic	1734 mm (W) x 320 mm (H) Size to be confirmed	1	48750	48750
5	Burger Tacos Co. Counter Side Wall		3M / LG Vinyl print pasted on back wall	659 mm (H) x 2168 mm (W)	1	4250	4250
6	Masala Kitchen Outlet Counter Signage		75 MM depth LED cut Black Aluminium Channel letters with 3mm White acyalic on top + 4 circles will be UV print on front milky white acrylic	2306 mm (W) x 300 mm (H)	1	41750	41750
7	Outside Façade Signage of Food Court (all 3 sides)		75 MM depth LED cut Black Aluminium Channel letters with 3mm White acyalic on top + for "F" use Red Colour Acrylic	500 mm (H) x 2676 mm (W)	3	37000	111000
8	Terminal F Outside Wall Artwork		3M / LG Vinyl print and fixed on 8mm HDMR board	Terminal F Outside Wall 1 (Right): 2700 mm (H) x 2760 mm (W) Terminal F Outside Wall 2 (Left): 2710 mm (H) x 2760 mm (W)	2	31750	63500
<b>Total</b>							<b>350650</b>
<b>PACKING &amp; TRANSPORT TO LKO</b>							
<b>INSTALLATION</b>							
<b>Grand Total</b>							<b>350650</b>