



BBN ENERGY SYSTEMS PVT. LTD.

(CPRI & ISO CERTIFIED)

Plot No. 234 Sector -37, Phase-VI, Udyog Vihar, Gurgaon -122001 (HR)

Mobiles: 9999516364, 9999876364, Telefax: 0124-4110987

E-mail: bbn.energysystems@gmail.com / info@bbnenergysystems.com

Website: www.bbnenergysystems.com

M/s. :- SM Infra service LLP

Address :-

E-mail :-

Kind Attn. :- Mr. Ashish Rawat

Offer No. :- BBN/2024-25/05/038

Offer Date :- 01-06-2024

Sub. - Offer for **Distribution Panel** as per your requirement

DISTRIBUTION PANEL			
S.No.	Description	Make	Qty.
A	ENCLOUSER:-		
1	DESIGNING, SUPPLYING, TESTING AND COMMISSIONING OF FOLLOWING FRONT OPERATED FLOOR MOUNTED IN DOOR TYPE SWITCH BOARDS FABRICATED OUT OF 16 GAUGE CRCA SHEET STEEL AND POWDER COATED (SIMENS GRAY 7035) APPROX SIZE 1800H*2500W*350D SQ. MM AND BASE	BBN	1
B	MAIN INCOMER :-		
1	125A TP 25KA MCCB (O/L & S/C) THERMAL MAGNETIC RELEASE	L&T/ABB/SCHNEIDER	1
2	125A TP SPREDER LINK	L&T/ABB/SCHNEIDER	1
3	EXTANDED ROTARY HANDLE	L&T/ABB/SCHNEIDER	1
4	3 PHASE KWH METER	TRINITY	1
5	2A SP MCB 10KA	L&T	3
6	INDICATING LIGHT RED, YELLOW	ESBEE	2
7	INDICATING LIGHT BLUE	ESBEE	1
8	CT 150/5 CLASS 1	TRINITY	3
9	NEUTRAL LINK	REPUTED	1
C	BUSBAR :-		
1	200AMP TPN 415 VOLTS COLOR CODED AL. BUSBAR	EC GRADE	1 SET
D	OUTGOING :-		
1	3 PHASE KWH METER	TRINITY	1
2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	32A TP POWER CONTACTOR (AC-1)	L&T	1
5	25A TP POWER CONTACTOR (AC-1)	L&T	1
6	10A SP MCB 10KA	L&T	2
7	25A SP MCB 10KA	L&T	1
8	ADD ON BLOCK 1NO+1NC	L&T	2
9	6A SP MCB 10KA	L&T	2
10	START/STOP PUSH BUTTON	ESBEE	4
11	ON INDICATING LIGHT	ESBEE	2
12	AUTO/MANUAL SELECTOR SWITCH	SALZER	2
13	NEUTRAL LINK	REPUTED	2
E	OUTGOING :-		

1	3 PHASE KWH METER	TRINITY	1
2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	25A TP POWER CONTACTOR (AC-1)	L&T	2
5	10A TP POWER CONTACTOR (AC-1)	L&T	1
6	10A SP MCB 10KA	L&T	6
7	6A SP MCB 10KA	L&T	2
8	ADD ON BLOCK 1NO+1NC	L&T	3
9	6A SP MCB 10KA	L&T	3
10	START/STOP PUSH BUTTON	ESBEE	6
11	ON INDICATING LIGHT	ESBEE	3
12	AUTO/MANUAL SELECTOR SWITCH	SALZER	3
13	NEUTRAL LINK	REPUTED	3
F	OUTGOING :-		
1	3 PHASE KWH METER	TRINITY	1
2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	16A SP MCB 10KA	L&T	3
5	NEUTRAL LINK	REPUTED	1
G	OUTGOING :-		
1	3 PHASE KWH METER	TRINITY	1
2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	63A TP MCB 10KA	L&T	2
5	50A TP POWER CONTACTOR (AC-1)	L&T	2
6	ADD ON BLOCK 1NO+1NC	L&T	2
7	6A SP MCB 10KA	L&T	2
8	START/STOP PUSH BUTTON	ESBEE	4
9	ON INDICATING LIGHT	ESBEE	2
10	AUTO/MANUAL SELECTOR SWITCH	SALZER	2
11	NEUTRAL LINK	REPUTED	2
H	OUTGOING :-		
1	63A TP MCB 10KA	L&T	1
I	OUTGOING :-		
1	3 PHASE KWH METER	TRINITY	1
2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	32A TP MCB 10KA	L&T	2
5	32A TP POWER CONTACTOR (AC-1)	L&T	2
6	ADD ON BLOCK 1NO+1NC	L&T	2
7	32A DP MCB 10KA	L&T	3
8	6A SP MCB 10KA	L&T	1
9	START/STOP PUSH BUTTON	ESBEE	2
10	ON INDICATING LIGHT	ESBEE	1
11	AUTO/MANUAL SELECTOR SWITCH	SALZER	1
12	NEUTRAL LINK	REPUTED	1
J	OUTGOING :-		
1	3 PHASE KWH METER	TRINITY	1

2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	63A TP MCB 10KA	L&T	2
5	32A TP POWER CONTACTOR (AC-1)	L&T	1
6	25A TP POWER CONTACTOR (AC-3)	L&T	1
7	ADD ON BLOCK 1NO+1NC	L&T	2
8	6-10A OVER LOARD RELAY	L&T	1
9	32A DP MCB 10KA	L&T	3
10	6A SP MCB 10KA	L&T	2
11	START/STOP PUSH BUTTON	ESBEE	4
12	ON INDICATING LIGHT	ESBEE	2
13	AUTO/MANUAL SELECTOR SWITCH	SALZER	2
14	NEUTRAL LINK	REPUTED	2
K	OUTGOING :-		
1	3 PHASE KWH METER	TRINITY	1
2	CT 60/5 CLASS 1	TRINITY	3
3	6A SP MCB 10KA	L&T	3
4	25A TP POWER CONTACTOR (AC-1)	L&T	2
5	16A TP POWER CONTACTOR (AC-1)	L&T	1
6	25A SP MCB 10KA	L&T	2
7	16A SP MCB 10KA	L&T	1
8	ADD ON BLOCK 1NO+1NC	L&T	3
9	6A SP MCB 10KA	L&T	3
10	START/STOP PUSH BUTTON	ESBEE	6
11	ON INDICATING LIGHT	ESBEE	3
12	AUTO/MANUAL SELECTOR SWITCH	SALZER	3
13	NEUTRAL LINK	REPUTED	3
L	OUTGOING :-		
1	25A DP MCB 10KA D-CURVE	L&T	2
2	32A DP MCB 10KA	L&T	1
M	OUTGOING :-		
1	63A FP MCB 10KA	L&T	1
2	3 PHASE KWH METER	TRINITY	1
3	CT 60/5 CLASS 1	TRINITY	3
4	6A SP MCB 10KA	L&T	3
5	25A TP POWER CONTACTOR (AC-1)	L&T	1
6	25A SP MCB 10KA	L&T	6
7	16A SP MCB 10KA	L&T	1
8	ADD ON BLOCK 1NO+1NC	L&T	1
9	6A SP MCB 10KA	L&T	1
10	START/STOP PUSH BUTTON	ESBEE	2
11	ON INDICATING LIGHT	ESBEE	1
12	AUTO/MANUAL SELECTOR SWITCH	SALZER	1
13	NEUTRAL LINK	REPUTED	1
N	MAIN INCOMER :-		
1	63A TPN MCB 10KA	L&T	1
2	6A SP MCB 10KA C-CURVE	L&T	3
3	APFC RELAY 8 STAGE	TRINITY	1

4	AUTO/MANUAL SELECTOR SWITCH	SALZER	1
5	AUX. CONTACTOR 2NO+2NC	L&T	2
6	ADD ON BLOCK	L&T	1
7	CT,S 60/5 CLASS -1 5VA	TRINITY	2
8	NEUTRAL LINK	REPUTED	1
0	BUSBAR :-		
1	100AMP TPN 415 VOLTS COLOR CODED AL. BUSBAR	EC GRADE	1 SET
P	CAPACITOR FEEDER 5KVAR :-		6
1	16A TP MCB 10KA	L&T	6
2	5KVAR CAPACITOR DUTY CONTACTOR	L&T	6
3	5KVAR CAPACITOR HEAVY DUTY	EPCOS	6
4	ON INDUCITION LIGHT	ESBEE	6
5	START STOP PUSH BUTTON	ESBEE	12
Q	MISCELLANEOUS :-		
1	Nuts, Bolts, Washers, Ferul Numbers, Cable Ties, Tie Base, Copper PVC Control Wire, Power Wire, Copper Thimbles, Panel Locks, I-Hooks, PVC Tape, Insulators E-type, L-Type , Round Type, MCB Chanel, Pvc Chanel, Connector Chanel,Connectors etc.	1 SET	1
	DISTRIBUTION PANEL		₹ 2,40,000.00

Terms & Conditions: -

- 1 **GST** :- Extra @ 18%
- 2 **Freight** :- Extra as per actual
- 3 **Payments** :- 50% along with the purchase order and balance against P.I.
- 4 **Delivery** :- 1-2 weeks after confirmed purchase order & payment
- 5 **Warranty** :- 12 months from date of supply
- 6 **Validity of Quotation** :- 15 Days

We hope that our offer is in line with your requirement and we look forward for a long terms association With you. If you want any more clarification, please feel free to contact us. Thanking You

For BBN ENERGY SYSTEMS PVT. LTD.

Ravinder Rohilla
Mob. 09999516364, 9999876364