

## DOMESTIC LOUNGE - PHASE 2

## CCTV BOQ

DATE : 26.06.2024

SR.NO	DESCRIPTION	UNIT	TOTAL QTY.	UNIT RATE	TOTAL AMOUNT
I	<b>CCTV SURVILLIANCE SYSTEM</b>				
1	Supply, Installation, Testing & Commissioning of <b>4 MP</b> Dome camera. IP-Based, 1/2.7" Progressive Scan CMOS 1920 × 1080 @ 25 fps Color: 0.01 Lux @ (F1.2; AGC ON), 0.02 Lux @(F1.6; AGC ON) 3.6 mm varifocal lens. H.265+, H.265, H.264+, H.264, BLC/3D DNR/ROI/HLC.	Nos.	60		
2	Supply, Installation, Testing & Commissioning (SITC) of 64 Channel Network Video Recorder. Recording at up to 12 MP resolution. HDMI Video output at up to 4K (3840 × 2160) resolution. H.265/ H.265+/H.264/ H.264+/MPEG4 video formats, supports audio compressions. Up to 4 SATA interfaces connectable for recording and backup. 1 self-adaptive 10 M/100 M/1000 Mbps network interface.Onvif Compliant. storage capacity to accommodate 30days storage, complete with all accessories as required.	Nos	1		
3	Supply, Installation, Testing & Commissioning (SITC) of 16 Channel Network Video Recorder. Recording at up to 12 MP resolution. HDMI Video output at up to 4K (3840 × 2160) resolution. H.265/ H.265+/H.264/ H.264+/MPEG4 video formats, supports audio compressions. Up to 4 SATA interfaces connectable for recording and backup. 1 self-adaptive 10 M/100 M/1000 Mbps network interface.Onvif Compliant. storage capacity to accommodate 30days storage, complete with all accessories as required.	Nos	R.O.		
4	VGA Flat screen LCD TFT 32" high resolution Monitor with power supply complete	No.	4		
5	16 TB Hard Disk (15 Days)	No.	1		
6	SITC of CAT 6 cable for PoE CCTV with GI conduit complete with saddle and accessories.	Mtr	2515		
7	12 port PoE 10/100/1000 Mbps layer 2 switches. PoE	No.	1		
8	24 port PoE 10/100/1000 Mbps layer 2 PoE switches.	No.	2		
	<b>TOTAL FOR CCTV SYSTEM</b>				<b>0</b>