

KUBER GAS TECH				
Description	UOM	Qty	Unit Price	Amount
PNG Pipeline				
Supply and Installation of 40NB (1-1 2 Dia) M.S. ERW Pipe IS-1239 with all required fittings such as elbow, tee, nipple etc. Jindal.	Rft	130	342	44460
Supply Installation of 1-1 2 Dia Main line Ball Valve Shut Off Valve screwed end.	Each	1	3211	3211
Supply Installation of 1-1 2 Dia Main line Solonoid Shut Off Valve screwed end.	Each	1	9600	9600
Supply Installation of 3 4 on off Valve for gas ranges screwed end.	Each	6	1233	7398
Supply Installation of 1-1 2 M.S. Clamps Supports for Pipeline.	Each	25	70	1750
Supply Installation of Hyd Flexible Hoses 1 2 5ft Long	Each	6	344	2064
Supply Installation of Hyd Flexible Hoses 1 2 7ft Long	Each	6	459	2754
Supply Installation of 1-1 2 Flange 150# with Stud Nuts and Gaskets.	Each	5	400	2000
Supply Installation of Hyd Adaptor for Valve 3 4 x 1 2 .	Each	6	98	588
Supply Installation of Safety Sign Boards as per MGL Standard.	Job	1	1500	1500
AutoCAD As Laid Drawing (Isometric) as per MGL Standard.	Set	1	3500	3500
Labour Charges for Pneumatic leak testing, Painting, transportation, commissioning of entire Gas Pipeline.	LS	1	4000	4000
TOTAL				82825