



SATTAVA AUTOMATION

Plot No.-10, K.H. No. - 865/2 &866/2, Chotti Bhati Chhattarpur New Delhi- 110074,
Mob No. 9818346264, 9540097202
Email ID- info@sattavaautomation.com, sattavaautomation@gmail.com,

| | | |
|--------------------|-----------|------------------|
| SM INFRA FARIDABAD | DATE | 10.06.2024 |
| | REF | |
| | QUOTATION | SM/LT/10/06_REVO |
| | K.A. | Mr. ASHISH RAWAT |

SUB: Techno-Commercial offer of LT Panel: -

Dear Sir,
We are pleased to quote you for your valuable Enquiry as below: -

| Sr. No. | Description | Qty. | Total Price (Rs) |
|---------|--|------|------------------|
| 1 | LT PANEL WITH CAPACITOR BANK 30KVAR | 01 | 2,45,000.00 |
| Sr. No. | Description | Qty. | Make |
| 1 | Section -1 Main Incomer | | |
| 1 | 125A TP MCCB 25KA O/L, S/C, Release | 1 | L&T |
| 2 | Spreader Links TP | 1 | L&T |
| 3 | Extended Rotary Handle | 1 | L&T |
| 4 | 2A MCB SP | 3 | L&T |
| 5 | RYB Phase Indication Lamp | 3 | L&T |
| 6 | 3 Ph. KWH Meter | 1 | Trinity |
| 7 | 150/5 CT's CL-1 | 3 | Reputed |
| 8 | Neutral Link | 1 | Reputed |
| A | OUTGOING-1 | | |
| 1 | Contactora 25A TP (AC-1) | 2 | L&T |
| 2 | Start/Stop PB | 4 | L&T |
| 3 | Add On Block | 2 | L&T |
| 4 | On Indication | 2 | L&T |
| 5 | SP MCB 32A 10KA | 2 | L&T |
| 6 | SP MCB 25A 10KA | 1 | L&T |
| 7 | A/M Selector Switch | 2 | Salzer |
| 8 | KWH Meter | 1 | Trinity |
| 9 | 30/5 CT's CL-1 | 18 | Reputed |
| 10 | Neutral Link | 1 | Reputed |
| B | OUTGOING-2 | | |
| 1 | Contactora 25A TP (AC-1) | 3 | L&T |
| 2 | Start/Stop PB | 6 | L&T |
| 3 | Add On Block | 3 | L&T |
| 4 | On Indication | 3 | L&T |
| 5 | SP MCB 10A 10KA | 6 | L&T |
| 6 | SP MCB 6A 10KA | 2 | L&T |
| 7 | A/M Selector Switch | 3 | Salzer |
| 8 | KWH Meter | 1 | Trinity |
| 9 | 30/5 CT's CL-1 | 3 | Reputed |
| 10 | Neutral Link | 1 | Reputed |
| C | OUTGOING-3 | | |
| 4 | SP MCB 16A 10KA | 3 | L&T |
| 7 | KWH Meter | 1 | Trinity |
| 8 | 60/5 CT's CL-1 | 3 | Reputed |
| 9 | Neutral Link | 1 | Reputed |
| D | OUTGOING-4 | | |
| 1 | Contactora 50A TP (AC-3) | 2 | L&T |
| 2 | Add On Block | 2 | L&T |
| 3 | Start/Stop PB | 4 | L&T |

| | | | |
|--------------------|--------------------------|---|---------|
| 4 | On Indication | 2 | L&T |
| 5 | TP MCB 63A 10KA | 2 | L&T |
| 6 | A/M Selector Switch | 2 | Salzer |
| 7 | KWH Meter | 1 | Trinity |
| 8 | 60/5 CT's CL-1 | 3 | Reputed |
| E | | | |
| OUTGOING-5 | | | |
| 1 | TP MCB 63A 10KA | 1 | L&T |
| F | | | |
| OUTGOING-6 | | | |
| 1 | Contactora 32A TP (AC-1) | 1 | L&T |
| 2 | Add On Block | 1 | L&T |
| 3 | Start/Stop PB | 2 | L&T |
| 4 | On Indication | 1 | L&T |
| 5 | TP MCB 32A 10KA | 1 | L&T |
| 6 | DP MCB 32A 10KA | 2 | L&T |
| 7 | A/M Selector Switch | 1 | Salzer |
| 8 | KWH Meter | 1 | Trinity |
| 9 | 60/5 CT's CL-1 | 3 | Reputed |
| G | | | |
| OUTGOING-7 | | | |
| 1 | 63A TP MCB 10KA | 1 | L&T |
| 2 | 3A TP Contactora (AC-1) | 1 | L&T |
| 3 | Start/Stop PB | 2 | L&T |
| 4 | On Indication | 1 | L&T |
| 5 | DP MCB 32A 10KA | 3 | L&T |
| 6 | A/M Selector Switch | 1 | Salzer |
| 7 | Contactora 25A (AC-3) | 1 | L&T |
| 8 | Overload Relay (6-10A) | 1 | L&T |
| 9 | Add On Block | 2 | L&T |
| 10 | Start/Stop PB | 2 | L&T |
| 11 | On Indication | 1 | L&T |
| 12 | KWH Meter | 1 | Trinity |
| 13 | 60/5 CT's CL-1 | 3 | Reputed |
| H | | | |
| OUTGOING-8 | | | |
| 1 | Contactora 25A TP (AC-1) | 3 | L&T |
| 2 | Add On Block | 3 | L&T |
| 3 | Start/Stop PB | 6 | L&T |
| 4 | On Indication | 3 | L&T |
| 5 | SP MCB 25A 10KA | 2 | L&T |
| 6 | SP MCB 16A 10KA | 1 | L&T |
| 7 | A/M Selector Switch | 3 | Salzer |
| 8 | KWH Meter | 1 | Trinity |
| 9 | 60/5 CT's CL-1 | 3 | Reputed |
| I | | | |
| OUTGOING-9 | | | |
| 1 | DP MCB 32A 10KA | 1 | L&T |
| 2 | DP MCB 25A 10KA | 1 | L&T |
| J | | | |
| OUTGOING-10 | | | |
| 1 | 63A 4P MCB 10KA | 1 | L&T |
| 2 | 3A TP Contactora (AC-1) | 1 | L&T |
| 3 | Start/Stop PB | 2 | L&T |
| 4 | On Indication | 1 | L&T |
| 5 | SP MCB 25A 10KA | 6 | L&T |
| 6 | A/M Selector Switch | 1 | Salzer |
| 12 | KWH Meter | 1 | Trinity |

| | | | |
|----------|-------------------------------------|----|----------|
| 13 | 100/5 CT's CL-1 | 3 | Reputed |
| K | CAPACITOR BANK- 30KVAR | | |
| 1 | MCB 63A TP+N | 1 | L&T |
| 2 | APFC Relay 8 Stage | 1 | Trinity |
| 3 | 100/5 CT's CL-1 | 2 | Reputed |
| 4 | Capacitor Duty Contactor 5kvar | 6 | L&T |
| 5 | Capacitor 5kvar | 6 | Trinity |
| 6 | Start/Stop PB | 12 | L&T |
| 7 | Control MCB SP 6A | 1 | L&T |
| 8 | On Indication | 6 | L&T |
| 9 | Aux. Contactor | 2 | L&T |
| 10 | Auto/Manual Selector Switch | 1 | L&T |
| 2 | Panel & Accessories | | |
| 1 | Cubical Box (1200(W)x2700(H)x350(D) | 1 | Sattava |
| 2 | Bus Bar 150A Al TPN | 1 | Hindalco |
| 3 | WIRING | | |
| | Wiring & Fixing Material | 1 | Reputed |

NOTE: - SCOPE OF WORK ONLY SUPPLY

Terms & Conditions: -

1. GST @ 18% Extra
2. Delivery: - 10-15 Days after technical & commercial clearance
3. One -year warranty against manufacturing defect.
4. Payment Terms: - 50% advance rest against PI
5. Freight: - It will be extra @ actual
6. Packing & Forwarding: - Wooden Packing will be Charge Extra, Transportation will be in your scope.

**With Regards,
Amit Kumar Singh**