



Electech Enterprises

ELECTRICAL CONTRACTOR & ENGINEERS

Date 29-08-2024

QUOTATION FOR DILLI STREAT @ DELHI AIRPORT

SR.NO	PARTICULARS	QTY	UNIT	RATE	AMOUNT
1	SITC of FRLS circuits pulled through GI conduits clamped on over head slab, laid over false ceiling or in wall chases.				
1.1	2X6.0 + 1X4.0 sq.mm. CU FRLS wires, circuit from DB or panel to power point (Equipment)	70	Mtrs	280	19600
1.2	4X4.0 + 1X2.5 sq.mm. CU FRLS wires, circuit from DB or panel to power point (Equipment)	90	Mtrs	450	40500
1.3	2X4.0 + 1X2.5 sq.mm. CU FRLS wires, circuit from DB or panel to power point (Equipment)	450	Mtrs	165	74250
1.4	2X2.5 + 1X1.5 sq.mm. CU FRLS wires, circuit from DB or panel to power point (Equipment) or switch board for lighting	325	Mtrs	135	43875
2	Supply & Laying of 6C x 4 sq mm Cu Armoured Cable for starter	40	Mtrs	800	32000
3	Supply & Laying of 4C x 16 sq mm Cu Armoured Cable for equipment	35	Mtrs	1050	36750
4	Supply & Laying of 4C x 6 sq mm Cu Armoured Cable for Equipment	160	Mtrs	580	92800
5	Supply & Laying of 4C x 4 sq mm Cu Armoured cable for AHU, Exhaust & Fresh Air	100	Mtrs	495	49500
6	Supply & Laying of 4+1 CCTV Cable	300	Mtrs	80	24000
7	Supply & Laying of Cat-6 Cable for Data	650	Mtrs	110	71500
8	Supply & Installation of 25mm Dia GI Conduit for CCTV & Data	150	Mtrs	240	36000
9	Supply & Installation of Rubber Mat	1	Nos	3500	3500
10	Supply & Installation of Shock Treatment Chart	1	Nos	2000	2000
11	Supply & Installation of Danger Notice Board	1	Nos	200	200
	TOTAL AMOUNT				5,26,475

Amount in words:- Five Lakhs Twenty Six Thousand Four Hundred and Seventy Five Only

