

PRE INVOICE

CONSIGNER :

THE OVEN FACTORY
 PLOT 31 OPP TO MANN HUMMEL MICO FACTORY
 ANTHARASANAHALLY , KIADB,
 PHASE 2, TUMKUR, KARNATAKA, INDIA 572106
 Ph - 9890911531 / 9449071531 www.theovenfactory.in
 OUR CST/TIN - 29480846558 DT/10/06/2009 GST #29ANEP6521C1Z3



SHIP TO:	TRAVEL FOOD SERVICES
STREET	AIRPORT T3
CITY	DELHI
STATE - COUNTRY	INDIA
Contact Person	MR SANDEEP BHAT
GST	27
PH Number	9821945599

BILL TO

P.I	TMK/24-25/175A
Date	6/5/2024

REF: INDIA MART

r. No	Description	REFRENCE PICTURES	QUANTITY 1
1	TOF - RRR WITH SKEWER HANGER (HEAT ROTATION REFLECTION & RETENTION TECHNOLOGY) - ELECTRIC BRICK OVEN - ROUND IGLOO 12" X 4 PIZZAS, BAKING CHAMBER SIZE: INNER 915 MM ROUND , OUTER DIA 1500 MM MOUNTED ON 915 MM HEIGHT TROLLEY WITH 152 MM RUBBER CAST IRON WHEELS, FABRICATED WITH SQ PIPES , MS RECTANGLE REINFORCED SECTIONS. INNER CONSTRUCTION WITH HAND CRAFTED HIGH ALUMINA BRICKS (40 %) ON METAL CASTABLE (SG) DOME FRAMES. IMPORTED PIZZA STONE 12.5 MM USED FOR BAKING AREA, INSULATED WITH GLASS WOOL & CERAMIC BLANKET. WIRE MESH & HIGH TEMPERATURE ADHESIVE TO PREVENT HEAT LOSSES. FINALLY OUTER BODY SEALED WITH 1.2 MM MS SHEET IN 22 PETAL SHAPED PIECES. FRONT DOOR & CHIMNEY FOR EXHAUST IS PROVIDED. ELECTRICAL COILS MADE OF KENTHAL ELEMENT RESISTANCE UPTO 450 DEGREE CELSIUS, SELEC MADE DIGITAL TEMPERATURE CONTROLLER, SPECIALLY DESIGNED KENDAL MADE HT 22 SWG WIRE COIL DRAWN AS PER THE BAKING CHAMBER WITH CERAMIC INSULATORS FOR GOOD HEAT RESISTANCE & UNIFORM HEAT ARRANGEMENT. POWER REQUIREMENT 15 KW, 3 PHASE 440 VOLTS, 4 WIRE SYSTEM WITH PROPER EARTHING TO BE PROVIDED. 2 REMOVABLE WOOD BURNING TRAYS PROVIDED. EXTERIOR FINISH OPTIONAL TILES. EASILY RELOCATABLE,APPROX WEIGHT - 1250 KGS, EXTERIOR FINISH RED BROKEN TILES	GRAVITY SPORTS CLUB HYDERABAD TELANGANA 	395,000.00
	SOMA VINE VILLAGE, NASHIK, AREA 51 CAFÉ HIDE OUT VIZAG AP,HIGH LAND CLUB, KOLHAPUR MAHARASTRA 	KOTTAYAM KERALA 	QUBE CAFÉ JAYNAGAR BLORE HAPPY PLACE BLORE
	VISUAL OF UNIQUE REFLECTOR TECHNIQUE INNER CHAMBER WITH METAL CASTABLE DOME OVERLAPPED WITH HAND CRAFTED HIGH ALUMINA REFRACTORY BRICKS & PIZZA STONE FOR BAKING BASE ----->>>		
	OVEN OUTER BOTTLE SHAPED DESIGN CHARGES		25,000.00
	ONSITE ASSEMBLY CHARGES		45,000.00
	PAYMENT TERMS: 60 % ADVANCE & BALANCE 40 % BEFORE DISPATCH FROM OUR WORKS. ORDER CANNOT BE CANCELLED ONCE PRODUCTION ORDER PROCESSED, NO REFUND OF ADVANCE IF DELIVERY NOT TAKEN BEFORE 180 DAYS OF WORK ORDER. WARRANTY: 2 year against any manufacturing defects excluding physical damages. 1 FREE service will be provided in warranty period. IN 1 free services visa. AIR / TRAIN FARE travelling , food, accommodation charges should be provided by the buyer without paying any spare OR SERVICE charges up to 12 months from the date on invoice. IF RE INSTALLATION REQUIRED FOR WARRANTY EQUIPMENT ALL CHARGES WILL BE APPLIED. PRE PAID SERVICE CHARGE INR.3500/ OVEN / DAY. PACKING & FORWARDING INCLUDED	CUSTOM REFERRED PIC 	
	ALL GOVERNMENT DOCUMENTS RELATED TO CUSTOM CLEARANCE TO BE PROVIDED 15 DAYS BEFORE DISPATCH OF THE EQUIPMENTS FROM OUR MANUFACTURING UNIT DISPATCH - 10 -15 DAYS FROM DATE OF WORK ORDER		
	CRANE, LABOUR & HANDLING CHARGES ON DELIVERY NOT OUR SCOPE		
	CARGO, CHAGES AT ACTUALS		30,000.00
		S TOTAL	495,000.00
		GST @ 18 %	EXTRA AT ACTUAL 89,100.00

INR FIVE LAKH EIGHTY FOUR THOUSAND ONE HUNDRED ONLY

584,100.00

FOR-THE OVEN FACTORY

OUR BANK DETAILS: CURRENT ACCOUNT
 THE OVEN FACTORY
 ICICI BANK LTD TUMKUR BRANCH
 C/A # 109405001896 RTGS / NEFT - ICIC0001094 - PROPRIETOR MR.B.R.PRASANNESH
 CST/TIN - 29480846558 DT/10/06/2009 GST #29ANEP6521C1Z3

OUR

Mr.B.R.Prasannesh