

Purchase Order

TRAVEL FOOD SERVICES LIMITED

Order Number : TFSP/PO/24-25/000014

Supplier Detail PIONEER PROJECT SOLUTION Supplier Code : RV232414136 [V0002345]	Shipped Location TRAVEL FOOD SERVICES LIMITED Delhi	Invoice Location TRAVEL FOOD SERVICES LIMITED Delhi
(V0002345)	New Terminal 1, Indira Gandhi International Airport, Domestic Departure SHA, Mehram Nagar, New Delhi, New Delhi, Delhi, 110037	New Terminal 1, Indira Gandhi International Airport, Domestic Departure Sha, Mehram Nagar, New Delhi, New Delhi, Delhi, 110037 GSTIN No : 07AADCB2762L2ZJ
PAN No : AHQPA6815Q Supplier GST No : 07AHQPA6815Q2ZQ Supplier Contact No : Contact Person Name : Mohd Ashraf Supplier Email : projectspioneer@gmail.com	Cost Center Code : 90192014 Cost Center Name : Dilli Streat Project ID : 0 PO Category : Capex NSO	Payment Term : Advance Payment - 50% along with work order. RA BILL - Up to 95% after work completion & submission of invoice. Retention 5% DLP till completion of 6 months. PO Creation Date : 02/04/2024 PO Approval Date : 08/04/2024 PO Currency : INR Buyer Name : Binu Balachandran

Sr. No	Item Code	HSN / SAC	Item Name	Item Description	Pur. Grp.	Qty	UOM	Basic Rate	Dis%	Net Rate	Total Amount	SGST %	CGST %	Gross Total Amount
1		8531	FAS	FAS	C01	1.00	NOS	125,050.00	0.00	125,050.00	125,050.00	9	9	147,559.00

Total Qty : 1.00

Total Basic PO Amount	125,050.00
Total Other Charges	
SGST Amount	11,254.50
CGST Amount	11,254.50
Grand Total PO Amount	147,559.00

Amount In Words : Rupees One Lakh Fourty Seven Thousand Five Hundred Fifty Nine Only

Remarks :

Standard Terms And Condition :

Completion / Delivery TimeLine : 3 Months

Mobilization Date : 10/04/2024

Defects Liability Period : 6 months

Retention Percentage : 5

Escalation Buyer Detail		
Name	Mobile No.	Email - ID
Jogeswar	9082949517	
Binu Balachandran	8452876061	

Disclaimer :

Point 1 : Unless informed to us it is assumed that you are not registered as MSME with the respective government authority. If you have not yet provided the MSME details along with proof kindly provide the same at the earliest. Alternatively once you get registered then provide us relevant proof to update our records.

Point 2 : Supplier is requested to acknowledge or decline the order within 24 hours or else it would be considered as accepted.

ItemCode :

ItemName : FAS

Sr No	Item Code	Item Name	UOM	Remarks	Quantity	Supplier Rate	Amount
1	B.1.1	Below ceiling level	Nos		5.00	4,200.00	21,000.00
2	B.3	Supply, Installation, Testing, and Commissioning of Addressable Type Fixed Temperature Heat Detector Conforming to EN54, with standard detector mounting base, IP30 Ingress Protection, Area Coverage of 50 sq. mm (subject to local standard), 360° Angle Visibility, Operating Temperature (-10°C to +50°C), approved by LPCB, of approved make with all necessary mounting and fixing arrangements.			0.00	0.00	0.00
3	B.6	Supply, Installation, Testing, and Commissioning of Addressable Type Monitor Module			0.00	0.00	0.00
4	B.7.1	Control Module	Nos		1.00	4,800.00	4,800.00
5	B.8	Supply, Installation, Testing, and Commissioning of Addressable Type Isolation Module			0.00	0.00	0.00
6	B.10.1	20 mm Dia	Mtr		0.00	10,000.00	0.00
7	B	FIRE ALARM SYSTEM (ADDRESSABLE TYPE)			0.00	0.00	0.00
8	B.1	Supply, Installation, Testing, and Commissioning of Addressable Type (Optical Smoke Heat) Multi Detector Conforming to EN54, with standard detector mounting base, IP30 Ingress Protection, Area Coverage of 50 sq. mm (subject to local standard), 360° Angle Visibility, Operating Temperature (-10°C to +50°C), approved by LPCB, of approved make with all necessary mounting and fixing arrangements.(Above Below Ceiling)			0.00	0.00	0.00
9	B.1.2	Above ceiling level	Nos		5.00	4,200.00	21,000.00
10	B.2.1	Below ceiling level	Nos		5.00	450.00	2,250.00
11	B.4	Supply, Installation, Testing, and Commissioning of Addressable Type Manual Call Point Conforming to EN54 with Break glass, ABS material enclosure, IP30 Ingress Protection, Operating Temperature (-10°C to +50°C) of approved make suitable for flush and surface mounting with all necessary mounting, termination and fixing arrangements.			0.00	0.00	0.00
12	B.5	Supply, Installation, Testing and commissioning of Addressable type Sounder Strobe with inbuilt Isolator operating temp (- 10 degree to + 55 degree) complete as required and duly approved by LPCB EN54.			0.00	0.00	0.00
13		FIRE ALARM SYSTEM - CABLING			0.00	0.00	0.00
14	B.2	Supply Installation Testing and Commissioning of Conventional Response Indicators(Below ceiling level)			0.00	0.00	0.00
15	B.3.1	Heat Detector - 58°C fixed temperature	Nos		4.00	4,700.00	18,800.00
16	B.6.1	Monitor Module	Nos		6.00	4,800.00	28,800.00
17	B.9.1	2 core 1.5 Sqmm	Mtr		0.00	50,000.00	0.00
18	B.10	Supplying, installing, testing and commissioning approved make PVC conduits on ceiling wall floor etc. complete with accessories like, Junction boxes, Collars, Bends etc.			0.00	0.00	0.00
19		FIRE ALARM SYSTEM - DETECTION DEVICES			0.00	0.00	0.00

20	B.4.1	Manual Call Point - (Wall Partition Mounted)	Nos		2.00	4,800.00	9,600.00
21	B.5.1	Sounder Strobe - (Wall Partition Mounted)	Nos		2.00	4,600.00	9,200.00
22		FIRE ALARM SYSTEM - MODULE DEVICES			0.00	0.00	0.00
23	B.7	Supply, Installation, Testing, and Commissioning of Addressable Type Control Module for shutting down FCU's, and magnetic fire door holders. Elevator recall, fire damper, pressurization fan, strobes etc			0.00	0.00	0.00
24	B.8.1	Isolation Module	Nos		2.00	4,800.00	9,600.00
25	B.9	Supply and surface laying of armoured FRLS twisted pair, shielded cable.			0.00	0.00	0.00
26		NOTE The quantities mentioned in the above BOQ includes services only inside the site location (building). If any termination of services required outside the site location contractor to verify at site and provide the quantity and cost over and above this BOQ.Any service penetration to be made good after installation. Fire sealing to be done for penetrations as per Airport requirement .			0.00	0.00	0.00
Total :					32.00		125,050.00