

Purchase Order

Deluxe Caterers Pvt. Ltd.

Order Number : DCPL/PO/24-25/000400

Supplier Detail BAY INTERIORS PRIVATE LIMITED Supplier Code : RV232420169 [RV232420169]	Shipped Location Deluxe Caterers Pvt. Ltd. CC M5 Ecity Mall	Invoice Location Deluxe Caterers Pvt. Ltd. CC M5 Ecity Mall
(RV232420169)	R1, 4th Floor, M5 Ecity Mall, Veerasandra Industrial Area, Electronic City, Bangalore – 560100	R1, 4Th Floor, M5 Ecity Mall, Veerasandra Industrial Area, Electronic City, Bangalore – 560100 GSTIN No : 29AAACD1685R1ZZ
PAN No : AAMCB0743L Supplier GST No : 09AAMCB0743L1ZE Supplier Contact No : 9548609567 Contact Person Name : Mehran Raza Supplier Email : bayinteriorsltd@gmail.com	Cost Center Code : CC M5 Ecity Mall Cost Center Name : CC M5 Ecity Mall Project ID : 0 PO Category : Capex NSO	Payment Term : Mobilization advance- Advance up 25% without GST against submission of cancelled cheque. RA Bill 1- Upto 60% upon work completions and join certification of RA Bill RA Bill 1- Upto 85% upon work completions and join certification of RA Bill Final Bill upto 95% upon final work completion and submission of final bill Retention of 5% to be released post completion of DLP or submission of BG PO Creation Date : 03/01/2025 PO Approval Date : 0 PO Currency : INR Buyer Name : Binu Balachandran

DRAFT

Sr.No	Item Code	HSN\SAC Code	Item Name	Item Description	Pur. Grp.	Qty	UOM	Basic Rate	Dis%	Net Rate	Total Amount	IGST %	Gross Total Amount
1	Electrical Work	9954	Electrical Works	Electrical Works	C01	1.00	EA	1,591,790.00	0.00	1,591,790.00	1,591,790.00	18	1,878,312.20

Total Qty : 1.00

Total Basic PO Amount	1,591,790.00
Total Other Charges	
IGST Amount	286,522
Grand Total PO Amount	1,878,312.20

Amount In Words : Rupees Eighteen Lakh Seventy Eight Thousand Three Hundred Twelve And Twenty Paise Only

Remarks : L1 vendor post auction

Standard Terms And Condition :

Completion / Delivery TimeLine : 31/01/2025

Mobilization Date : 06/01/2025

Defects Liability Period : 30/06/2025

Retention Percentage : 5

Escalation Buyer Detail		
Name	Mobile No.	Email - ID
Abdul R	+91 99202 92129	
Binu Balachandran	8452876061	

Disclaimer :

Point 1 : Unless informed to us it is assumed that you are not registered as MSME with the respective government authority. If you have not yet provided the MSME details along with proof kindly provide the same at the earliest. Alternatively once you get registered then provide us relevant proof to update our records.

Point 2 : Supplier is requested to acknowledge or decline the order within 24 hours or else it would be considered as accepted.

DRAFT

ItemCode : Electrical Work

ItemName : Electrical Works

Sr No	Item Code	Item Name	UOM	Remarks	Quantity	Supplier Rate	Amount
1		10 sq.mm x 4 core Copper Armoured Cable - Supply and Installation Connection of 1100 V Grade Armoud Cable Having Sector Circular Shaped Aluminium Copper Conductor PVC insulated Cores, Laid Up, PVC Tape Wrapped Inner Sheathed, GI Strip Wire Armoured And Over All Extruded PVC Sheathed Confirming To IS 1554, Laid On Wall) Ceiling Using GI Clamps And Spacer As Per Route Shown At Site And Further As Directed By Consultant At Site in the following size.	Mtr		35.00	770.00	26,950.00
2		16 sq.mm x 4 core Copper Armoured Cable - Supply and Installation Connection of 1100 V Grade Armoud Cable Having Sector Circular Shaped Aluminium Copper Conductor PVC insulated Cores, Laid Up, PVC Tape Wrapped Inner Sheathed, GI Strip Wire Armoured And Over All Extruded PVC Sheathed Confirming To IS 1554, Laid On Wall) Ceiling Using GI Clamps And Spacer As Per Route Shown At Site And Further As Directed By Consultant At Site in the following size.	Mtr		160.00	960.00	153,600.00
3		Supply and installation testing commission of - 16A 10kA SP MCB	Nos		65.00	320.00	20,800.00
4		Supply Installation testing commission of following 16 way SPN DB Box Fixing with Proper Cable Tie and Lugs Fixing	Nos		1.00	2,650.00	2,650.00
5		Supply and installation testing commission of following LT make VFD PANEL suitable motors (FOR KITCHEN EXHAUST FRESH AIR BLOWER) 5 HP VFD - 2 Nos, 7.5 HP VFD - 1 Nos and One Dol starter provision	Nos		1.00	160,000.00	160,000.00
6		Main LT Panel - Supply Installation Testing Commissioning of 3Ph, 415V, 50Hz Main LT Panel 1 as per SLD	Nos		1.00	255,000.00	255,000.00
7		Supply and installation of 20 mm MS Conduit including Chasing and Refilling the Trench As per the Rout Shown in the drawing and approved by Consultant at site including clamping and closing the Open Pipe and Temporarily by suitable And Covers Against Entry of Dust or any Other Foreign Materials.	Mtr		700.00	172.00	120,400.00
8		Supply and installation of 25 mm MS Conduit including Chasing and Refilling the Trench As per the Rout Shown in the drawing and approved by Consultant at site including clamping and closing the Open Pipe and Temporarily by suitable And Covers Against Entry of Dust or any Other Foreign Materials.	Mtr		500.00	212.00	106,000.00
9		Installation of Insect Killer	Nos		2.00	500.00	1,000.00
10		Supply Installation connection testing and commission of following 2 Core Flexible WIRE Copper Conductor PVC insulated Wires Pulled Through Heavy Gauge Laid Concealed over False Ceiling Orin Wall Chases for Speaker And SubWoofers. (Within Existing conduit) - Music System	Mtr		180.00	65.00	11,700.00
11		Supply and installation of concealed wiring using 2 x 4 sqmm, 1 x 2.5 sq.mm FRLS Copper Conductor PVC Insulated wires (with proper R.Y.B. Colour Code)Laid Concealed Over false Ceiling or in wall chases Proper Fixing	Mtr		250.00	171.00	42,750.00

12		6 sq.mm x 4 core Copper Armoured Cable - Supply and Installation Connection of 1100 V Grade Armoud Cable Having Sector Circular Shaped Aluminium Copper Conductor PVC insulated Cores, Laid Up, PVC Tape Wrapped Inner Sheathed, GI Strip Wire Armoured And Over All Extruded PVC Sheathed Confirming To IS 1554, Laid On Wall) Ceiling Using GI Clamps And Spacer As Per Route Shown At Site And Further As Directed By Consultant At Site in the following size.	Mtr		160.00	430.00	68,800.00
13		Supply and installation testing commission of - 40 A 2pole 30ma DP + RCBO	Nos		3.00	2,950.00	8,850.00
14		Supply and installation testing commission of - 32A 4 Pole 100ma TPN MCB	Nos		2.00	4,500.00	9,000.00
15		Supply and installation connection of G.I 25mm x 6mm Earthing Patti	Mtr		95.00	141.00	13,395.00
16		Supply and installation testing commission of - 40 A 4 Pole 100ma TPN MCB	Nos		1.00	4,700.00	4,700.00
17		Supply and installation connection Testing and commissioning of following 1.5 sq.mm x 2 core Copper Armoured Cable for FAS System	Mtr		105.00	145.00	15,225.00
18		50 sq.mm x 3.5 coreXLPE INSULATED ALUMINIUM ARMORED CABLE - Supply and Installation Connection of 1100 V Grade Armoud Cable Having Sector Circular Shaped Aluminium Copper Conductor PVC insulated Cores, Laid Up, PVC Tape Wrapped Inner Sheathed, GI Strip Wire Armoured And Over All Extruded PVC Sheathed Confirming To IS 1554, Laid On Wall) Ceiling Using GI Clamps And Spacer As Per Route Shown At Site And Further As Directed By Consultant At Site in the following size.	Mtr		10.00	735.00	7,350.00
19		Supply Fixing of - 10 sq.mm x 4 core Glands	Nos		2.00	150.00	300.00
20		Supply and installation testing commission of - 10A 10kA SP MCB	Nos		41.00	320.00	13,120.00
21		Supply and installation testing commission of - 32A 2pole 30ma DP + RCBO	Nos		3.00	2,500.00	7,500.00
22		Supply and installation testing commission of - 25A 2pole 30ma DP + RCBO	Nos		7.00	2,500.00	17,500.00
23		Supply and installation testing commission of - 63A 4 Pole 100ma TPN MCB	Nos		1.00	4,900.00	4,900.00
24		Supply Installation testing commission of following 6 way TPN DB Box Fixing with Proper Cable Tie and Lugs Fixing	Nos		1.00	5,600.00	5,600.00
25		Supply and punching of double compression gland of 6 sq.mm x 4 core Glands	Nos		24.00	184.00	4,416.00
26		Supply and installation testing commission of - 25A 10kA SP MCB	Nos		6.00	320.00	1,920.00
27		Supply and punching of double compression gland of 16 sq.mm x 4 core Glands	Nos		8.00	238.00	1,904.00
28		Supply Installation testing commission of following 16 way TPN DB Box Fixing with Proper Cable Tie and Lugs Fixing	Nos		1.00	8,700.00	8,700.00
29		Supply Installation of - 10 Modular plate with box	Nos		4.00	360.00	1,440.00
30		Installation, testing commissioning of - SPOT LIGHT 1 - LT1	Nos		10.00	100.00	1,000.00
31		Supply Installation of - 5 15A 5 pin socket	Nos		15.00	225.00	3,375.00
32		BULB - LT6	Nos		56.00	75.00	4,200.00
33		Supply Installation of - 5 15A 5 pin switch	Nos		15.00	165.00	2,475.00
34		Exhaust Motor Connection	Nos		2.00	500.00	1,000.00

35		Supply Installation of - Data Socket	Nos		15.00	650.00	9,750.00
36		Installtion of Air Curtain	Nos		2.00	500.00	1,000.00
37		Supply Installation of - Blank Plate	Nos		12.00	30.00	360.00
38		Supply and fixing of 100mm x 100mm Casing Box	Mtr		25.00	850.00	21,250.00
39		Supply Fixing of - 4 sq.mm Pin Type Lugs (Alluminium)	Nos		12.00	20.00	240.00
40		Supply Installation of - 8 Modular Surface Box	Nos		5.00	110.00	550.00
41		Supply Fixing of - 16 sq.mm Pin Type Lugs (Alluminium)	Nos		8.00	35.00	280.00
42		Supply and installation of 150mm x 150 mm Junction Box with SS Cover plate	Nos		2.00	500.00	1,000.00
43		Supply Fixing of - 16 sq.mm x 4 core Glands	Nos		2.00	155.00	310.00
44		Supply and Installation connection Testing and commissioning of following Cat 6 Data Cable Wire (Data Voice)	Mtr		525.00	70.00	36,750.00
45		Supply Fixing of - 50 sq.mm x 3.5 core Glands	Nos		2.00	250.00	500.00
46		Supply and installation testing commission of following 1 no.of 4way weather proof box fixing for outdoor unit cable lugs proper fixing	Nos		4.00	1,675.00	6,700.00
47		Supply Fixing 15 A Top	Nos		15.00	125.00	1,875.00
48		Supply and Installation of Ceiling Rose	Nos		45.00	25.00	1,125.00
49		Supply and installation connection testing and commissioning of following 3 Face 5 TPN 32 A Socket, With Box and 3 Face Top,32A 4pole TPN MCB complete fixing	Nos		2.00	6,000.00	12,000.00
50		Installation, testing commissioning of - HANGING LIGHT 2 - LT8	Nos		1.00	200.00	200.00
51		Installation, testing commissioning of - WALL MOUNTED - LT9	Nos		8.00	150.00	1,200.00
52		Installation, testing commissioning of - TRACK LIGHT - TL1 (Legnth - 900mm)	Nos		10.00	150.00	1,500.00
53		Fresh Air Motor Connection	Nos		2.00	500.00	1,000.00
54		Supply Installation of - 6 Modular plate with box	Nos		13.00	250.00	3,250.00
55		Supply Installation of - 2 Modular plate with box	Nos		2.00	130.00	260.00
56		Supply and fixing of 150mm x 150mm Casing Box	Mtr		35.00	1,850.00	64,750.00
57		Supply Fixing of Lugs Punching	Nos		0.00	0.00	0.00
58		Supply Fixing of - 6 sq.mm Ring Type Lugs (Alluminium)	Nos		24.00	22.00	528.00
59		Supply Fixing of - 50 sq.mm Ring Type Lugs (Alluminium)	Nos		4.00	55.00	220.00
60		Supply Fixing of - 4 sq.mm x 4 core Glands	Nos		3.00	80.00	240.00
61		Supply Installation of - USB charging Sockets	Nos		10.00	1,100.00	11,000.00
62		Supply and installation of 100mm x 100 mm Junction Box with SS Cover plate	Nos		2.00	350.00	700.00
63		Supply fixing of 300mm x 50mm x 2mm thick perforated cable tray.	Mtr		30.00	1,350.00	40,500.00
64		Supply fixing of 150mm x 50mm x 2mm thick perforated cable tray.	Mtr		45.00	850.00	38,250.00
65		Rubber Mat	Nos		2.00	1,500.00	3,000.00

66		Supply and installation of 20 mm Flexible MS Conduit including Chasing and Refilling the Trench As per the Rout Shown in the drawing and approved by Consultant at site including clamping and closing the Open Pipe and Temporarily by suitable And Covers Against Entry of Dust or any Other Foreign Materials.	Mtr		70.00	42.50	2,975.00
67		Supply and installation of 25 mm Flexible MS Conduit including Chasing and Refilling the Trench As per the Rout Shown in the drawing and approved by Consultant at site including clamping and closing the Open Pipe and Temporarily by suitable And Covers Against Entry of Dust or any Other Foreign Materials.	Mtr		70.00	52.50	3,675.00
68		Supply and installation of concealed wiring using 2 x 2.5 sqmm, 1 x 1.5 FRLS Copper Conductor PVC Insulated wires (with proper R.Y.B. Colour Code)Laid Concealed Over false Ceiling or in wall chases Proper Fixing	Mtr		885.00	110.00	97,350.00
69		Supply and installation of concealed wiring using 3 X1.5 sqmm FRLS Copper Conductor PVC Insulated wires (with proper R.Y.B. Colour Code)Laid Concealed Over false Ceiling or in wall chases Proper Fixing	Mtr		580.00	75.00	43,500.00
70		4 sq.mm x 4 core Copper Armoured Cable - Supply and Installation Connection of 1100 V Grade Armoud Cable Having Sector Circular Shaped Aluminium Copper Conductor PVC insulated Cores, Laid Up, PVC Tape Wrapped Inner Sheathed, GI Strip Wire Armoured And Over All Extruded PVC Sheathed Confirming To IS 1554, Laid On Wall) Ceiling Using GI Clamps And Spacer As Per Route Shown At Site And Further As Directed By Consultant At Site in the following size.	Mtr		45.00	360.00	16,200.00
71		Supply Installation testing commission of following 8 way TPN DB Box Fixing with Proper Cable Tie and Lugs Fixing	Nos		2.00	5,800.00	11,600.00
72		Supply and installation testing commission of following single phase 20A metal cladde socket and MCB with top and box	Nos		8.00	1,450.00	11,600.00
73		Supply and installation testing commission of following 6 16A switch and socket Connector Stip	Nos		25.00	65.00	1,625.00
74		Installation, testing commissioning of - SPOT LIGHT 2 - LT2	Nos		23.00	100.00	2,300.00
75		Installation, testing commissioning of - 2 X 2 CEILING MOUNT LIGHT- 3000K - LT3	Nos		4.00	250.00	1,000.00
76		Installation, testing commissioning of - 2 X 2 CEILING MOUNT LIGHT-6000K - LT4	Nos		12.00	250.00	3,000.00
77		Installation, testing commissioning of - LED COVE LIGHT - LT5	Mtr		12.00	65.00	780.00
78		Installation, testing commissioning of - HANGING LIGHT 1 - LT7	Nos		4.00	200.00	800.00
79		TUBELIGHT (Legnth - 1200mm) (Supply Installation)	Nos		4.00	400.00	1,600.00
80		Supply and fixing of 75mm x 75mm Casing Box	Mtr		25.00	450.00	11,250.00
81		Supply Fixing of - 10 sq.mm Pin Type Lugs (Alluminium)	Nos		8.00	32.00	256.00
82		Supply Fixing of - 6 sq.mm x 4 core Glands	Nos		6.00	80.00	480.00
83		Supply and punching of double compression gland of 4 sq.mm x 4 core Glands	Nos		12.00	150.00	1,800.00
84		Supply and punching of double compression gland of 10 sq.mm x 4 core Glands	Nos		8.00	234.00	1,872.00
85		Supply and punching of double compression gland of 50 sq.mm x 3.5 core Glands	Nos		4.00	376.00	1,504.00
86		Supply Fixing 5 A Top	Nos		5.00	75.00	375.00

87		Supply Installation of - 8 Modular plate (Horizontal) with box	Nos		1.00	310.00	310.00
88		Supply Installation of - 4 Modular plate with box	Nos		2.00	195.00	390.00
89		Supply Installation of - 3 Modular plate with box	Nos		16.00	165.00	2,640.00
90		Supply Installation of - 16A switch socket metal Box	Nos		13.00	250.00	3,250.00
91		Supply Installation of - 5 15A 3 pin socket	Nos		10.00	185.00	1,850.00
Total :					5,188.00		1,591,790.00

DRAFT