

<b>HYD FF 27 Pizza Hut</b>	<b>Pioneer Project (R0)</b>	<b>Pioneer Project (R1)</b>
<b>HVAC - high side - supply</b>	<b>1,25,000</b>	<b>1,25,000</b>
<b>HVAC - high side - Installation</b>	<b>10,000</b>	<b>10,000</b>
<b>Hvac - low side</b>	<b>1,92,200</b>	<b>1,82,100</b>
	<b>3,27,200</b>	<b>3,17,100</b>

Sr No.	Item Code	Item Description	UOM	Qty	Pioneer Project (R0)		Pioneer Project (R1)		Bench marking	PO Reference	
					Unit Price	Amount	Unit Price	Amount			
1		HVAC - high side - supply	NOS	1		1,25,000		1,25,000			
1	1	Electrostatic Air Cleaners									
2		MAKE RYDAIR									
3	a	AIRFLOW 2500 CFM (L)650 x (W)1250 x (H)550	Nos	1	1,25,000	1,25,000	1,25,000	1,25,000	1,45,000	PO/23-24/100104	HYD CF 005 Taco Bell
2		HVAC - high side - Installation	NOS	1		10,000		10,000			
4	1	Electrostatic Air Cleaners									
5		Installation, testing and comissioning									
6	a	AIRFLOW 2500 CFM (L)650 x (W)1250 x (H)550	Nos.	1	10,000	10,000	10,000	10,000	rate analysis		
3		Hvac - low side	NOS	1		1,92,200		1,82,100			
7	1	AIR DISTRIBUTION SYSTEM									
8	1.1	GI sheet metal rectangular duct									
9		Supply, Fabrication, Installation, Testing Commissioning of following gauges of ducting complete with splitters, necessary supports, dampers, and turning vanes as per specification and HVAC layout. Aproved Makes JINDAL, TATA, SAIL, Equivalent. All exposed ducts and supports shall be painting with 2 coats of primer 2 coats of epoxy paint. (Make-JSW ESSAR)									
10	a	24 gauge ducting - 0.63 mm thickness (Width upto - 750mm)	Sq. mt	70	1,250	87,500	1,250	87,500	1350.00	PO/24-25/CAP/10343	HYD FF018 Carls Jr.
11	b	22 gauge ducting - 0.80 mm thickness (Width 751 - 1500)	Sq. mt	5	1,450	7,250	1,450	7,250	1550.00	PO/24-25/CAP/10343	HYD FF018 Carls Jr.
12	3	XLPE Insulation (Supply Exhaust Fresh Air Duct)									
13		Providing and fixing XLPE insulation by applying adhesive on ducts complete as per specifications and drawings. Make-SUPREME PARAMOUNT. (Exhaust- out side insulation, Fresh air -outside insulation, Supply- Inside insulation, Supply-outside painted.)									
14	a	13 mm thick	Sq. mt	55	650	35,750	650	35,750	750.00	PO/24-25/CAP/10343	HYD FF018 Carls Jr.
15	4	Continous Linear Grilles									
16		Extruded Aluminium Powder Coated Continous Linear Grilles Of Required Airflow Angles (0 15 30 45 degree deflection 1 or 2 way) with four side flanges as per requirements. (Make - AIRVISION COSMOS)									
17	a	6 Width	Rmt	10	1,800	18,000	1,450	14,500	1,650	PO/23-24/100104	HYD CF 005 Taco Bell
18	b	8 Width	Rmt	3	2,200	6,600	1,650	4,950	rate analysis		
19	7	Canvass Connection									
20	a	Installation of Double Canvass connection for all air outlet inlet, Fire retardant type with GI flanges for Units.	Nos.	2	3,000	6,000	2,650	5,300	2,500	PO/23-24/100104	HYD CF 005 Taco Bell
21	8	Volume Control Damper (make - Cosmos Caryaire Air Product)									
22		Supply Installation of volume control damper made of 100x40x1.55mm thk galvanised steel frame with opposed blades of 1.55mm galvanised sheet steel.	Sq. mt	2	6,500	13,000	6,500	13,000	7,500	PO/23-24/100104	HYD CF 005 Taco Bell
23	9	Supply Air Gypsum 4 way Diffuser (Diffuser to be mounted on collar with damper)									
24		Supply, installation of aluminium extruded white powdercoated four way square diffuser with damper. Make-AIRVISION COSMOS									
25	a	Neck Size - 12 x 12 (Outer Size - 15 x 15)	Nos.	4	2,400	9,600	2,400	9,600	3,000	PO/23-24/100104	HYD CF 005 Taco Bell
26	10	Collar Damper (make - Cosmos Caryaire Air Product)									
27	a	Supply Installation of Collar Damper gear operated with vertical blades.	Sq. mt	1	8,500	8,500	4,250	4,250	5,500	PO/23-24/100104	HYD CF 005 Taco Bell