

| BILL OF QUANTITY | | | | | | | |
|---|---|--|------|-----|-----------|---|--|
| SECTION 04 - SIGNAGES, LOGOS & DISPLAY WORK | | | | | | | |
| NO. | Pictures | ITEM DESCRIPTION | UNIT | QTY | UNIT RATE | AMOUNT INR | SPECS CONSIDERED / REMARKS |
| | | SECTION 04 - SIGNAGES, LOGOS & DISPLAY WORK | | | | | |
| | | The Contractor is referred to the Specifications and Drawings for all details related to this Section of the works and he is to include for complying with all the requirement contained therein, whether or not they are specifically mentioned within the Items description. THE CONTRACTOR TO SHARE SHOP DRAWINGS FOR ALL SIGNAGE FOR APPROVAL | | | | | |
| 1.00 | | SIGNAGES & DISPLAY UNIT | | | | | |
| | | Install Signages with necessary wiring, conduits in accordance with the drawings and specification & Airport Regulations. All signages sample to be provided for review and approval. | | | | | |
| 1.01 |  | STREET PIZZA LOGO AT FRONT ELEVATION: Supply & Installation of STREET PIZZA front lit aluminium 3D logo, letter made of aluminium channellume 3D letters with front face acrylic illuminated LED with transformer, including the Vinyle graphic base & structure . To be hunged from the top, as per the drawings & renders, approx size 900x1200mm Supply and fixing of LED controller for adjusting LED brightness. <i>Note: contractor to share shop drawings for approval and Material to be approved by Clients Team.</i> | Nos | 1 | 25,000 | 25,000 | |
| | | Above mentioned logo in the Marathi language with the same material and specification | Nos | 1 | 25,000 | 25,000 | |
| 1.02 |  | STREET PIZZA LOGO IN THE DINING AREA WALL: Supply & Installation of AJ1881 front lit aluminium 3D logo, letter made of aluminium channellume 3D letters with front face acrylic illuminated LED with transformer, as per the drawings & renders, approx size 750x900mm Supply and fixing of LED controller for adjusting LED brightness. <i>Note: contractor to share shop drawings for approval and Material to be approved by Clients Team.</i> | Nos | 2 | 19,500 | 39,000 | |
| 1.03 |  | BACK LIT PANEL IN DINING AREA WALL: Supply & Installation of back lit display panel with advertisement graphics as shown in the render. Supply and fixing of LED controller for adjusting LED brightness. SIZE: 3900X1700MM. <i>Note: contractor to share shop drawings for approval and Material to be approved by Clients Team.</i> | Nos | 1 | 99,500 | 99,500 | Considered: Backlit LED lit Aluminium profile Fabric Box |
| 1.04 |  | BACK LIT PANEL IN FRONT ELEVATION: Supply & Installation of back lit display panel with advertisement graphics as shown in the render. Supply and fixing of LED controller for adjusting LED brightness. SIZE: 2680X2185MM. <i>Note: contractor to share shop drawings for approval and Material to be approved by Clients Team.</i> | Nos | 1 | 95,000 | 95,000 | Considered: Backlit LED lit Aluminium profile Fabric Box |
| 1.05 |  | BACK LIT LETTERS ABOVE LIVE KITCHEN: Supply & installation of back lit acrylic letters projected from wall as shown in drawing and renders. Supply and fixing of LED controller for adjusting LED brightness, approx size height of letters is 300mm. <i>Note: contractor to share shop drawings for approval and Material to be approved by Clients Team.</i> | Nos | 1 | 41,500 | 41,500 | |
| 1.06 |  | BACK LIT LETTERS ABOVE BAR AREA: Supply & Installation of back lit acrylic letters projected from wall as shown in drawing and renders. Supply and fixing of LED controller for adjusting LED brightness, approx size height of letters is 300mm <i>Note: contractor to share shop drawings for approval and Material to be approved by Clients Team.</i> | Nos | 1 | 41,500 | 41,500 | |
| | | | | | | | |
| | | | | | | Sub-total | 3,66,500 |
| | | | | | | Packing & Transportation | 15,000 |
| | | | | | | Installation | 30,000 |
| | | | | | | Grand Total | 4,11,500 |
| | | | | | | With GST 18% Extra | 4,85,570 |
| | | SECTION 04 - SIGNAGES, LOGOS & DISPLAY WORK | | | | | |
| | | Generally | | | | | |
| 2.00 | | The Contractor will list here & price of any items shown on the drawings, mentioned in the Specifications or required for the satisfactory completion of this section, but not mentioned in above BOQ list. Any such items not listed below shall be deemed to be included : | | | | | |
| | | | | | | | |
| | | | | | | Sub-total | |
| | | | | | | Total Section 4 - Carried to Summary | |