







S.No	AREA	ARTWORK REFERENCE	ITEM/ DESCRIPTION	SIZE	QTY.	Look and Feel		Rate Rs.	Rates with installation Loaded	REMARKS
1	Front Outside Main Façade		Reverse Lit Letters/Halo Lit Letters S5304 Hairline-Gold PVD 1mm thick, 25 mm depth Gold Metal Letters, Halo fit with 3000K Warm White Samsung LED module, back side hidden 3mm Backlit white Astari make Acrylic to cover the LEDs and S5304 Studs and spacers	7864 mm (W) x 728 mm (H) All letters sizes mentioned in the artwork	1		AREA Front Outside Main Façade ITEM/ DESCRIPTION Reverse Lit Letters/Halo Lit Letters S5304 Hairline-Gold PVD 1mm thick, 25 mm depth Gold Metal Letters, Halo fit with 3000K Warm White Samsung LED module, back side hidden 3mm Backlit white Astari make Acrylic to cover the LEDs and S5304 Studs and spacers	2,34,500	2,64,500	Wire looping to be kept ready as per our template
3	Front Non-lit Signage Removal		Relocate the signage from the front façade to the side façade, replacing the existing Dollop installation	-	1	-	AREA Front Non-lit Signage Removal ITEM/ DESCRIPTION Relocate the signage from the front façade to the side façade, replacing the existing Dollop installation SIZE -	7,500	7,500	REFITTING ONLY- REMOVAL EXCLUDED
2	Back Outside Façade		Removing of Existing Signage & Do proper Packing and Handover to client, New Signage with Reverse Lit Letters/Halo Lit Letters S5304 Hairline-Gold PVD 1mm thick, 25 mm depth Gold Metal Letters, Halo fit with 3000K Warm White Samsung LED module, back side hidden 3mm Backlit white Astari make Acrylic to cover the LEDs and S5304 Studs and spacers	3800 mm (W) x 352 mm (H) All letters sizes mentioned in the artwork	1		AREA Back Outside Façade ITEM/ DESCRIPTION Removing of Existing Signage & Do proper Packing and Handover to client, New Signage with Reverse Lit Letters/Halo Lit Letters S5304 Hairline-Gold PVD 1mm thick, 25 mm depth Gold Metal Letters, Halo fit with 3000K Warm White Samsung LED module, back side hidden 3mm Backlit white Astari make Acrylic to cover the LEDs and S5304 Studs and spacers	1,10,000	1,25,000	Wire looping to be kept ready as per our template
4	Side Signage Removal and Replace with Front Non-lit Signage		Removing of Existing Signage & Do proper Packing and Handover to client, Replace the Dollop on the side façade with the signage removed from the front façade (as per Point No. 3)	-	1	-	AREA Side Signage Removal and Replace with Front Non-lit Signage ITEM/ DESCRIPTION Removing of Existing Signage & Do proper Packing and Handover to client, Replace the Dollop on the side façade with the signage removed from the front façade (as per Point No. 3) SIZE -	7,500	7,500	REFITTING ONLY- REMOVAL EXCLUDED
							TOTAL	3,59,500	4,04,500	
	General Comments		Rates (Filled in as other charges on procurements) Total Rs.65,000/-				Packing (2 New Signs)	6,000	6,000	
	Scaffold to be arrange by Signage Vendor		40,000				Transportation (2 New Signs)	6,000	6,000	
	Passes & Escort to be arrange through Nexus		-				Installation Charges (2 New Signs & 2 Refitting)	45,000	LOADED	
	Working Hour 10pm to 4am - After Working hour everyday Scaffold to be dismantle & kept at Secure area		10,000				GRAND TOTAL Rs.	4,16,500	4,16,500	
	Site Debris & Packaging Boxes to be discard by Signage vendor		10,000				GRAND TOTAL Rs. WITH GST	4,91,470	4,91,470	
	Electrical Supply will be available rest Connection to be done by signage vendor									
	Signage material to be receive & Shift at site by Signage Vendor		5,000							